



# **STREETS AND TRAFFIC BYLAW**

## **BYLAW NO. 09-079**

This consolidation is a copy of a bylaw consolidated under the authority of section 139 of the *Community Charter*.  
(Consolidated on June 18, 2026 up to Bylaw 26-044)

This bylaw is printed under and by authority of the Corporate Administrator of the Corporation of the City of Victoria.

NO. 09-079

**STREETS AND TRAFFIC BYLAW****A BYLAW OF THE CITY OF VICTORIA**

(Consolidated to include Bylaws No. 10-061, 10-074, 12-030, 13-083, 14-023, 14-051, 14-096, 15-042, 16-013, 16-068, 16-089, 18-058, 19-040, 19-048, 19-067, 20-033, 21-056, 21-111, 22-028, 22-088, 23-045, 23-048, 23-054, 23-106, 24-024, 24-046, 24-077, 25-046, 26-005, 26-024, 26-044)

The purpose of this Bylaw is to consolidate, update, and clarify the regulations applicable to streets and traffic.

***Contents*****26-024 PART 1 - INTRODUCTION**

- 1 Title
- 2 Application of Bylaw
- 3 Interpretation
- 4 Definitions
- 5 Classification of streets
- 6 Procedures for orders by Director of Engineering
- 7 Powers of Council not affected by an order
- 8 Orders exempt from procedures

**PART 2 - TRAFFIC**

- 9 Powers of Director of Engineering
- 10 Jaywalking
- 11 School Patrols
- 12 Firefighters may direct traffic
- 13 Work in streets
- 14 Moving vehicle into traffic
- 15 Traffic at intersections
- 16 Temporary traffic control devices by police
- 17 Speed zones
- 18 Use of street by buses
- 19 Police traffic direction
- 20 Obeying traffic controls
- 21 Stop signs
- 22 Green light
- 23 Yellow light
- 24 Red light
- 25 Green arrow
- 26 Flashing lights
- 27 Stunting
- 28 Driving on laned roadway
- 29 Highway lines
- 30 Highway lines exception
- 31 Newly painted lines

- 32 Duty when overtaking
- 33 Passing on right
- 34 Passing on left
- 35 Clear view on passing
- 36 Divided highways
- 37 Reverse turn
- 38 Signals on turning
- 39 Means of signalling
- 40 Left hand drive signals
- 41 Driving over fire hose
- 42 Driving on sidewalk
- 43 Cyclist provisions
- 43A Skating provisions
- 44 Motorcycles

### **PART 3 - PARKING AND STOPPING**

- 45 Powers of Director of Engineering - parking and stopping zones
- 46 Powers of Director of Engineering - traffic control devices
- 47 Impounding and tow away zones
- 48 No stopping zone
- 49 No parking zone
- 50 No parking in City lane
- 51 Limited time parking zone
- 52 Limited time parking exemption permit
- 53 Residential parking zone
- 54 Residential parking permit zone
- 55 Truck loading zone
- 56 Hotel zone
- 57 General loading zone
- 58 School loading zone
- 59 Church loading zone
- 60 Parking and loading zones for handicapped persons
- 61 Taxi stand
- 62 Transit zone
- 63 Shuttle bus zone
- 64 Out of town tour bus zone
- 65 Safety zone
- 66 Angle parking
- 67 Reserved parking area
- 68 Special parking zone
- 69 No parking (vehicles over 6m) zone
- 70 Passenger zone
- 71 Parking meter zone
- 72 Pay Station Zone
- 72A Electric vehicle charging zone
- 24-077 72B Car share co-op parking zone
- 72C Shared micromobility parking zone
- 24-046 73 Parking exemptions for persons with disabilities
- 74 Passenger Directed Vehicle in Metered or Pay Station Zone
- 75 Trailers in metered spaces

- 76 Temporary discontinuance and reservation of metered space
- 76A Exemption for car share vehicles
- 77 Lawful coins required in parking meter and pay station
- 78 Ticket controlled parking zones
- 79 Sightseeing vehicle stands
- 80 Reserved stand for horsedrawn sightseeing vehicles
- 81 [repealed]
- 82 Vehicle standing while loading or unloading
- 83 Night parking
- 84 Sleeping in vehicles
- 85 Distance between parked vehicles
- 86 Parking on one way street
- 87 Miscellaneous stopping, standing, parking
- 88 Curb parking
- 89 Stopping at intersections
- 90 Yellow curb lines

#### **PART 4 - VEHICLE SIZE AND WEIGHT**

- 91 *Motor Vehicle Act* regulations apply
- 92 Vehicle size and weight
- 93 *Commercial Transport Act* regulations apply to all vehicles
- 94 Engineer's report for permit

#### **PART 5 - GENERAL REGULATIONS**

- 95 Parking commercial vehicle in residential zone
- 96 Trailer left on street
- 97 Driving between vehicles in funeral procession
- 98 Air horn
- 99 Procession in street requires permit
- 100 Commercial goods on street
- 101 Excavations, obstructions on street require permit
- 102 Objects prohibited on streets
- 102A Portable signs
- 103 Obstructing sidewalk, soliciting, fighting
- 103A Boulevards and medians
- 104 Fireworks
- 105 Liquids onto street require permit
- 105A Electric vehicle charging infrastructure on street
- 106 Works on street require permit
- 106A Damage to survey monument fee
- 107 Clearing sidewalk of snow and ice
- 108 Placing wood on a street
- 109 Paint, posters on street structure
- 110 Parking on sidewalk or boulevard requires permit
- 111 Driving on sidewalk permitted in special circumstances
- 112 Trees on and near streets
- 113 Private streets and lanes require sign
- 114 Cycles on sidewalks, bicycle helmets
- 115 Skating on sidewalk

26-044 116 [repealed]

## **PART 6 - ADMINISTRATION AND ENFORCEMENT**

117 Chalk mark on vehicle tire  
 26-044 118 [repealed]  
 119 Offence  
 120 Penalties  
 121 Offence notice  
 122 Voluntary Penalties  
 123 Repeal

Schedule A – Street Classifications

Schedule B – Speed Zones

Schedule C – [repealed]

Schedule D – Truck and Commercial Routes

Schedule E – Minimum Fines for Traffic Offences

Schedule F – Minimum Fines for Traffic Offences other than Sections 19 to 44

Schedule G – Voluntary Penalties Payable under Offence Notices

BL 23-054 Schedule H – [repealed]

Schedule I – Conditions

The Council of the Corporation of the City of Victoria enacts the provisions in this Bylaw under its statutory powers, which include

- (a) sections 8, 35 to 46, 62, 64, 194, and 260 to 263 of the *Community Charter*;
- (b) sections 124, 209, and 214 of the *Motor Vehicle Act*;
- (c) section 14 of the *Victoria City Act, 1919*;
- (d) section 24 of the *Victoria City Act, 1920*;
- (e) section 19 of the *Victoria City Act, 1923*;
- (f) section 9 of the *Victoria City Act, 1934*.

## **PART 1 - INTRODUCTION**

### **Title**

- 1 This Bylaw may be cited as the "STREETS AND TRAFFIC BYLAW".

### **Application of Bylaw**

- 2 (1) The provisions of this Bylaw in relation to drivers of vehicles also apply to all of the following:
- (a) persons riding a cycle or an animal;
  - (b) persons driving an animal drawn vehicle.

- (2) The provisions of this Bylaw do not apply to any of the following:
- (a) persons, vehicles or other equipment while lawfully engaged in highway or public utility construction, maintenance or repair work on, over or under the surface of a highway;
  - (b) the driver of an emergency vehicle that is
    - (i) responding to an emergency call,
    - (ii) sounding an emergency siren (audible siren, signal bell or exhaust whistle), and
    - (iii) showing an emergency light (flashing red or blue light);
  - (c) the driver of an emergency vehicle that is
    - (i) at the scene of an emergency, and
    - (ii) showing an emergency light (flashing red or blue light);
  - (d) a police officer who is in the immediate pursuit of an actual or suspected violator of the law;
  - (e) a police officer who is engaged in a police duty of a nature that the sounding of a siren or other audible signal would unduly hamper the performance of that duty.
- (3) Where anything in this section conflicts with B.C. Reg. 133/98, the Emergency Vehicle Driving Regulation under the *Motor Vehicle Act* (the "Regulation"), the Regulation prevails.

### Interpretation

- 3 (1) In this Bylaw and orders made under it, the words and expressions used have the meanings given to them by the *Motor Vehicle Act* and its regulations, except as otherwise specified in this bylaw.
- (2) Despite subsection (1) and subject to subsection (3), the definitions in section 4 and elsewhere in this bylaw prevail over the definitions in the *Motor Vehicle Act* and its regulations if they are inconsistent, except as otherwise specified in this bylaw.
- (3) Despite subsections (1) and (2) and section 4, the definitions and interpretation provisions of the *Motor Vehicle Act* and its regulations apply to the words and expressions used in Part 2.

### 26-024 Definitions

- 4 In this Bylaw

24-024 "air horn"

means a device or contrivance used or intended to be used for the emission of sound by means of the forced passage of air or gas through that device or contrivance;

"arterial highway"

has the same meaning as in the *Transportation Act*;

"boulevard"

means that portion of a street between the curb lines or the lateral lines of a roadway and the adjoining property line, excluding a sidewalk;

"bus"

means a railless vehicle used as a public utility for the carriage of passengers;

"car share co-op vehicle"

means a vehicle owned by a not-for-profit co-operative association incorporated under the laws of British Columbia and used exclusively in the provisions of the association's car sharing service;

24-077

"car share EV station"

means a battery charging station that is available for car share co-op vehicles for the purpose of transferring electric energy to a battery or other energy storage device in an electric vehicle;

"charging station"

means a battery charging station that is available for public use for the purpose of transferring electric energy to a battery or other energy storage device in an electric vehicle or shared micromobility device;

"City"

means the Corporation of the City of Victoria;

"City lane"

means a public highway which is not designed for general travel and which is used primarily as a means of access to the rear of properties;

"commercial vehicle"

means a truck or van that is used primarily for the purpose of freight transportation and that displays

- (a) a valid and subsisting commercial licence plate issued under the *Commercial Transport Act*, and

- (b) a valid and subsisting licence plate issued under Division 2 of Part 20 of the *Local Government Act*, other than farm vehicles as defined in the regulations made under the *Commercial Transport Act*;

"continuously parked"

means a vehicle that is parked without being moved from a particular City block;

"council"

means the elected council of the City of Victoria;

"director"

in reference to the head of a City department or other City official, means the person appointed to that position or a successor position with the same responsibilities as the position designated in this bylaw;

"driveway crossing"

means the improved section of a curb, sidewalk or boulevard constructed to provide vehicular access to one or more lots from a street;

"dwelling"

means a building used by one or more persons as a residence, but does not include any of the following types of dwelling:

- (a) a hotel, hostel, or other transient accommodation facility,
- (b) a place of detention;

"electric vehicle"

means a vehicle that operates, either partially or exclusively, on electrical energy from an off-board source that is stored on-board for motive purposes, but does not include vehicles that cannot be licensed by the Insurance Corporation of British Columbia;

"electric vehicle charging zone"

means any street or part of it that has been designated and identified for the exclusive use of electric vehicles;

"elephant's feet markings"

means two parallel lines of white intermittent squares on the surface of the street;

"holiday"

includes any of the following days:

- (a) Sunday,
- (b) Boxing Day, British Columbia Day, Canada Day, Christmas Day, Easter Monday, Good Friday, Labour Day, New Years Day, Remembrance Day, Thanksgiving Day, Truth and Reconciliation Day, Victoria Day, and
- (c) any day set by the Parliament of Canada, by the Legislature, or by proclamation of the Governor General or the Lieutenant Governor to be observed as a day of general prayer or mourning, a day of public rejoicing or thanksgiving, a day for celebrating the birthday of the reigning Sovereign, or as a public holiday;

"metered space"

- (a) where a parking meter stand has only one parking meter head, means that rectangular portion of the adjacent curb lane measuring
  - (i) not less than 4.8 m nor more than 10.4 m from the centre of the base of the parking meter stand in the direction counter to the direction of the curb lane traffic, and
  - (ii) 2.5 m from the curb in a roadward direction;
- (b) where a parking meter stand has two parking meter heads,
  - (i) with regard to the parking meter head first in sequence in the direction of the curb lane traffic, means that rectangular portion of the adjacent curb lane that is described in paragraph (a), and
  - (ii) with regard to the parking meter head second in sequence in the direction of the curb lane traffic, means that rectangular portion of the adjacent curb lane measuring
    - (A) not less than 4.8 m nor more than 10.4 m from the centre of the base of the parking meter stand in the direction of the curb lane traffic, and
    - (B) 2.5 m from the curb in a roadward direction;
- (c) where a parking meter is installed adjacent to a curb lane which is marked with parallel angular lines or other markings forming parallel angular lines, means that portion of the curb lane designated for the accommodation of a vehicle by the lines or markings and being nearest to the applicable meter head;

"metered zone"

means any street or part of it

- (a) that is designated as a metered zone under this Bylaw, and
- (b) on which a parking meter has been erected to control parking;

“mobile bicycle vendor”

means a person who sells goods from a cycle;

“multi-use trail”

means a trail intended and marked for general and recreational use by the public, including cyclists, but excluding motor vehicles.

"park", "parking", or "parked"

means the standing of a vehicle, whether occupied or not, on a street, except when the vehicle is standing temporarily for the purpose of, and while actually engaged in loading or unloading;

"parking meter"

means a parking meter stand equipped with a single or double parking meter head;

"parking meter head"

means a mechanical or electronic appliance designed for the purpose of gauging and indicating a time within which a vehicle is or may be parked;

"parking meter stand"

means a pole or stand supporting a single or double parking meter head;

“parking pay station”

means a device operated and maintained by or on behalf of the City for collecting parking fees for parking in, and controlling the use of, parking spaces.

"parking space"

means any portion of a street marked by any one or more of the following to indicate that it is intended for the parking of a vehicle: painted lines, a number, meter, pole or other device.

“passenger directed vehicle”

has the same meaning as in the Business Licence Bylaw;

BL 23-054

BL 23-054  
24-046

"passenger vehicle"

means a vehicle that is not a commercial vehicle, a sightseeing vehicle, a bus or a taxi;

“pay station zone”

means a street or a portion of a street designated as such under this bylaw where parking is permitted subject to payment of a charge at a parking pay station.

“person with disabilities”

means a person whose mobility is limited as a result of a permanent or temporary disability that makes it impossible or difficult to walk;

“police chief”

means the person appointed from time to time as the chief of the City of Victoria Police Department.

"police officer"

means a peace officer, constable or person having the powers of a peace officer or constable;

"private lane"

- (a) means every way or place that is privately owned and used for vehicular travel by the owner of that way or place, and by those having the express or implied permission of the owner, and
- (b) excludes a driveway between a single residence and a street;

“protected bicycle lane”

means a lane on a street separated from the general purpose travel lane by a buffer and a vertical element including a median, curb or flexible delineator;

"public place"

includes all public squares, public gardens, public recreation grounds, parks, lanes and streets within the City;

26-044

"semi-trailer"

includes

- (a) a vehicle without motive power designed to be drawn by a motor vehicle or truck tractor and so constructed that an appreciable part of its weight and that of its load rests on and is carried by the motor vehicle or truck tractor; and
- (b) a pole trailer;

“shared micromobility device”

means a cycle that is publicly accessible for a fee and supplied by a shared micromobility service provider;

“shared micromobility parking zone”

means a street or a portion of a street designated under this bylaw for the exclusive use of shared micromobility devices;

“shared micromobility service provider”

means an entity contracted by the City to operate, manage and supply a system of shared micromobility devices to the public;

"sidewalk"

means the part of a highway that has been improved for pedestrian traffic and, where there is no boulevard between the nearest building and that part of a highway, the sidewalk is deemed to abut that building unless proved otherwise;

"sightseeing vehicle"

- (a) means a cab, carriage, omnibus, cart, wagon, dray, truck, motor car, automobile or other conveyance or vehicle that operated by a driver and used primarily for sightseeing purposes,
- (b) includes a horsedrawn vehicle, and
- (c) excludes a passenger directed vehicle;

BL 23-054

"stop" or "stand"

- (a) when required by this bylaw, means a complete cessation from movement, and
- (b) when prohibited, means the stopping or standing of a vehicle, whether occupied or not, except when that is necessary to avoid conflict with other traffic or to comply with the directions of a police officer or traffic control device;

"street"

includes a highway, as defined in the *Motor Vehicle Act*;

"street line"

means the dividing line between real property and an adjoining street;

“taxi”

BL 23-054

24-046

means a passenger directed vehicle that is operated under a licence pursuant to the *Passenger Transportation Act* (BC) that expressly authorizes the driver to transport passengers who hail the passenger directed vehicle from the street, or who cause the passenger directed vehicle to be hailed from the street;

"ticket dispenser"

means an automatic or other mechanical meter erected, maintained or operated

- (a) on a street or portion of a street, and
- (b) for the purpose of allotting and controlling parking spaces for vehicles by the dispensing of tickets or coupons to the drivers of vehicles parked or intended to be parked in those parking spaces;

24-024

"traffic control plan"

has the same meaning as in the British Columbia Ministry of Transportation and Infrastructure document titled "2020 Traffic Management Manual for Work on Roadways", as amended from time to time;

24-024

"traffic management plan"

has the same meaning as in the British Columbia Ministry of Transportation and Infrastructure document titled "2020 Traffic Management Manual for Work on Roadways", as amended from time to time;

"trailer"

means a vehicle, including a semi-trailer, that is at any time drawn upon a street by a motor vehicle, excluding:

- (a) an implement of husbandry;
- (b) a sidecar attached to a motor vehicle; or
- (c) a disabled motor vehicle that is towed by a tow car;

"transit zone"

means a street or a portion of a street designated under this bylaw for the exclusive use of designated buses;

"weapon"

includes all types of firearms, air guns, air rifles, air pistols and spring guns.

"works"

means works owned or operated by the City.

### **Classification of streets**

- 5 Streets are classified in accordance with Schedule A.

### **Procedures for orders by Director of Engineering**

- 6 (1) Subject to section 8, an order made by the Director of Engineering under a power delegated by this Bylaw must
- (a) be in writing and signed by the Director of Engineering;
  - (b) be forwarded to the Corporate Administrator;
  - (c) come into effect immediately, unless a later date is specified in the order.
- (2) The Director of Engineering may forward an order, that in the Director of Engineering's opinion concerns a new matter, to the Corporate Administrator with a request that the order be presented
- (a) to the appropriate committee of Council for consideration; or
  - (b) to City Council for ratification.
- (3) The committee that considers an order may present it, with or without a recommendation, to the Council for its ratification or other action.
- (4) An order forwarded to City Council for ratification comes into force immediately on ratification unless a later date is specified in the order.
- (5) The Director of Engineering may exercise the power to make an order under this Bylaw at any time or from time to time, as the Director of Engineering considers necessary or expedient.

### **Powers of Council not affected by an order**

- 7 (1) The giving or delegating of authority, under this Bylaw, to the Director of Engineering does not limit the power of the Council to initiate, adopt, repeal or amend bylaws in respect of any matter within this Bylaw.
- (2) An order made by the Director of Engineering is valid and effective only to the extent that it is not inconsistent with or repugnant to the provisions of a bylaw.
- (3) The Council may, by bylaw, at any time rescind or revoke an order made by the Director of Engineering.

### **Orders exempt from procedures**

- 8 (1) Section 6 does not apply to
- (a) an order made under section 76 or 82, or

- (b) the issuance of a permit or the granting of a permission or consent, under this Bylaw, by the Director of Engineering or any other of the City's officers or employees who are empowered to issue the permit or grant the permission or consent.
- (2) An order referred to in subsection (1) or an order for the rescission, revocation, amendment or variation of that order must take effect at the time it is made or at the time stipulated by the order.

## **PART 2 - TRAFFIC**

### **Powers of Director of Engineering**

- 9 For the purpose of regulating the movement of traffic, the Director of Engineering may make orders designating any of the following matters:
  - (a) the intersections where signs bearing words or symbols indicating that U-turns are prohibited must be placed;
  - (b) the locations at intersections where signs bearing words or symbols indicating that left hand turns are prohibited must be placed;
  - (c) the locations at intersections of not more than two streets where signs bearing words or symbols indicating that the driver of a vehicle which is facing the red light at that intersection must not cause the vehicle to make a left turn into a street on which traffic is restricted to one direction of travel;
  - (d) the locations at intersections where signs bearing the words "Stop" must be placed;
  - (e) the locations at or near intersections where signs, bearing words or symbols indicating that drivers must yield, must be placed;
  - (f) the locations where traffic control signals described in section 126 of the *Motor Vehicle Act* must be placed;
  - (g) the intersections where signs bearing words or symbols indicating that a street is a one way street must be placed, together with other signs the Director of Engineering considers advisable in order to prohibit traffic proceeding in more than one direction on a one way street;
  - (h) the portions of streets that are crosswalks and that the crosswalks must be marked by distinctive lines or markers on street surfaces, and the locations where signs, indicating the locations of crosswalks, must be placed;
  - (i) the roadway or part of a roadway, on a street, that must be a laned roadway within the meaning of the *Motor Vehicle Act*, and must be marked with suitable lines on the roadway;
  - (j) the lane or lanes on a laned roadway at or near an intersection where suitable traffic control devices must be placed to direct that no turns or turns only in

certain directions may be made at the intersection by vehicles travelling in the lane or lanes;

- (k) streets or portions of streets which must be marked with lines in the manner provided by section 155 of the *Motor Vehicle Act*;
- (l) streets or portions of streets which must be divided in the manner described by section 163 of the *Motor Vehicle Act*;
- (m) the locations at or in the vicinity of schools and public playgrounds for children where signs stating a speed limit of 30 km/h, or on which the numeral "30" is prominently shown, must be displayed for the purposes of section 147 of the *Motor Vehicle Act*;
- (n) the locations at intersections where signs bearing words or symbols indicating that right hand turns are prohibited must be placed
- (o) the unmarked crosswalks where signs indicating that pedestrian traffic is prohibited must be placed;
- (p) the streets or portions of streets on which buses that may be a hazard to other users by reason of their size or operating characteristics are prohibited, and the locations where signs indicating that bus traffic is prohibited must be placed;
- (q) for the purpose of preventing a hazard or damage to streets,
  - (i) designate limits for the gross weight of a vehicle or its load, and for the distribution of loads of vehicles,
  - (ii) designate all or part of a street from which vehicles are prohibited if they exceed the limits designated under subparagraph (i), and
  - (iii) designate locations for the placement of signs that indicate the limits and prohibitions designated under subparagraphs (i) and (ii);
- (r) the streets or portions of streets where traffic, classes of traffic, vehicles, or drivers are regulated as the Director of Engineering considers advisable to support the prioritization of pedestrian traffic including:
  - (i) the hours during which and days on which a provision of an order concerning the streets or portions of streets is in effect; and
  - (ii) different provisions, including exceptions, for different classes of traffic, vehicles, or drivers;
- (s) the streets or portions of streets where traffic, classes of traffic, vehicles or drivers are regulated as the Director of Engineering considers advisable to support the prioritization of cycle traffic including different provisions, including exceptions, for different classes of traffic, vehicles or drivers.

### **Jaywalking**

- 10      (1)      That part of the City bounded by the east side of Douglas Street, the south side of Fort Street, the west side of Government Street, and the north side of Herald Street is designated as a congested district.
- (2)      A pedestrian must not traverse or cross any of the streets within a congested district at any place other than in a crosswalk.
- (3)      The provisions of subsections (1) and (2) do not apply to any of the following areas:
- (a)      that portion of Fisgard Street between Government Street and Douglas Street;
- (b)      that portion of Government Street between Fort Street and Yates Street.
- (4)      Despite subsections (1) to (3), a person must not traverse or cross a street in an unmarked crosswalk where a sign is displayed which indicates that pedestrian traffic is prohibited.

### **School patrols**

- 11      (1)      The principal of a public or private school may appoint a number of pupils of the school, or other persons, as members of a traffic patrol with the power to require vehicles to stop at crosswalks in the vicinity of schools by displaying flags or other devices bearing the word "Stop".
- (2)      A driver of a vehicle approaching a crosswalk must not cause or permit the vehicle to proceed through or into the crosswalk when a member of a traffic patrol appointed under subsection (1) displays a flag or other device with the word "Stop" on it facing the traffic approaching from either direction.

### **Firefighters may direct traffic**

- 12      (1)      An officer or member of the Fire Department in attendance at or near any fire or other emergency may direct traffic on a street in the vicinity of the fire or other emergency.
- (2)      A person must comply with directions given under subsection (1).

### **Work in streets**

- 13      Without making a formal order, the Director of Engineering may direct that, on any street where construction, reconstruction, widening, repair, marking or any other work is being done, traffic control devices must be erected or placed for any of the following purposes:
- (a)      to indicate that crews or equipment are working on the street;
- (b)      to regulate or prohibit traffic in the vicinity of the work;
- (c)      to limit the rate of speed of vehicles in the vicinity of the work.

### **Moving vehicle into traffic**

- 14 The driver of a vehicle may move it from a stationary position at a curb or the edge of a roadway into the line of vehicular traffic on the street only if the driver
- (a) first signals an intention to do so by means of an hand and arm signal or a mechanical signal, as prescribed for turns by the *Motor Vehicle Act*, and
  - (b) has ascertained that the movement can be made in safety, having regard to the nature, condition and use of the street and the traffic which actually is at the time, or might reasonably be expected to be, on the street.

### **Traffic at intersections**

- 15 Despite a traffic control indication to proceed, a person may drive a vehicle into an intersection or a marked crosswalk only if there is sufficient space on the other side of the intersection or crosswalk to accommodate the vehicle without obstructing the passage of other vehicles or pedestrians.

### **Temporary traffic control devices by police**

- 16 A police officer may place or employ temporary traffic control devices that the police officer considers necessary to assist in controlling traffic.

### **Speed zones**

- 26-024 17 (1) A person must not drive a motor vehicle in excess of the maximum rate of speed prescribed in Schedule B for the street, lane or the part of a street or lane listed or shown in Schedule B under that rate of speed.
- (2) The maximum rates of speed prescribed in Schedule B apply to all motor vehicles except where a type of motor vehicle is specified in Schedule B in respect of a specified street or lane or part of a street or lane.
- (3) The Director of Engineering must cause signs to be erected or placed on streets and lanes or the parts of them designated in Schedule B for the purpose of indicating the speed limits prescribed under this section and Schedule B.

### **Use of street by buses**

- 18 The driver of a bus must not drive it on a street on which bus traffic has been prohibited by an order made under section 9(p).

### **Police traffic direction**

- 19 If a police officer reasonably considers it necessary to
- (a) ensure orderly movement of traffic,
  - (b) prevent injury or damage to persons or property, or
  - (c) permit proper action in an emergency,

the police officer may direct traffic according to his or her discretion and, despite anything in to the contrary in sections 20 to 44, a person must obey the police officer's directions.

### **Obeying traffic controls**

- 20 Unless otherwise directed by a police officer or a person authorized by a police officer to direct traffic, every driver of a vehicle and every pedestrian must obey the instructions of an applicable traffic control device.

### **Stop signs**

- 21 Except when a police officer directs otherwise, if there is a stop sign at an intersection, a driver of a vehicle must stop
- (a) at the marked stop line, if any,
  - (b) before entering the marked crosswalk on the near side of the intersection, or
  - (c) when there is neither a marked crosswalk nor a stop line, before entering the intersection, at the point nearest the intersecting highway from which the driver has a view of approaching traffic on the intersecting highway;

### **Green light**

- 22 (1) When a green light alone is exhibited at an intersection by a traffic control signal,
- (a) the driver of a vehicle facing the green light
    - (i) may cause the vehicle to proceed straight through the intersection, or to turn left or right, subject to a sign or signal prohibiting a left or right turn, or both, or designating the turning movement permitted;
    - (ii) must yield the right of way to pedestrians lawfully in the intersection or in an adjacent crosswalk when the green light is exhibited; and
    - (iii) must yield the right of way to vehicles lawfully in the intersection when the green light is exhibited; and
  - (b) a pedestrian facing the green light may proceed across the roadway in a marked or unmarked crosswalk, subject to special pedestrian traffic control signals directing him or her otherwise, and has the right of way for that purpose over all vehicles.
- (2) When a green light alone is exhibited at a place other than an intersection by a traffic control signal,
- (a) the driver of a vehicle
    - (i) may cause the vehicle to pass the signal, and

- (ii) must yield the right of way to a pedestrian still in the roadway or on a crosswalk in the vicinity of the signal when the green light is exhibited;
- (b) a pedestrian still in the roadway or on a crosswalk in the vicinity of the signal when the green light is exhibited must proceed as quickly as possible from the roadway; and
- (c) a pedestrian must not enter the roadway in the vicinity of the signal until either
  - (i) the traffic control signal facing the vehicular traffic exhibits a red light, or
  - (ii) a traffic control signal instructs the pedestrian that he or she may cross the roadway.

### **Yellow light**

- 23      (1)      When a yellow light alone is exhibited at an intersection by a traffic control signal, following the exhibition of a green light,
- (a) the driver of a vehicle approaching the intersection and facing the yellow light must cause it to stop before entering the marked crosswalk on the near side of the intersection, or if there is no marked crosswalk then before entering the intersection, unless the stop cannot be made in safety;
  - (b) a pedestrian facing the yellow light must not enter the roadway; and
  - (c) a pedestrian proceeding across the roadway and facing the yellow light exhibited after the pedestrian entered the roadway
    - (i) must proceed to the sidewalk as quickly as possible, and
    - (ii) has the right of way for that purpose over all vehicles.
- (2)      When a yellow light alone is exhibited at a place other than an intersection by a traffic control signal,
- (a) the driver of a vehicle approaching the signal must cause it to stop before entering the nearest marked crosswalk in the vicinity of the signal, or if there is no marked crosswalk, before reaching the signal, unless the stop cannot be made in safety; and
  - (b) a pedestrian must not enter the roadway in the vicinity of the signal until either
    - (i) the traffic control signal facing the vehicular traffic exhibits a red light, or

- (ii) a traffic control signal instructs the pedestrian that he or she may cross the roadway.

### Red light

- 24 (1) Subject to subsection (2), when a red light alone is exhibited at an intersection by a traffic control signal, the driver of a vehicle approaching the intersection and facing the red light must cause it to stop before entering the marked crosswalk on the near side of the intersection, or if there is no marked crosswalk, before entering the intersection, and subject to the provisions of subsection (2), must not cause the vehicle to proceed until a traffic control signal instructs the driver that he or she is permitted to do so.
- (2) The driver of a bus approaching an intersection and facing a red light and a prescribed white rectangular indicator may cause the bus to proceed through the intersection.
- (3) Despite subsection (1), and except when a right turn permitted by this subsection is prohibited by a sign at an intersection, the driver of a vehicle facing the red light, and in obedience to it is stopped as closely as practicable to a marked crosswalk on the near side of the intersection, or if there is no marked crosswalk then as closely as practicable to the intersection, may cause the vehicle to make a right turn, but the driver must yield the right of way to all pedestrians and vehicles lawfully proceeding as directed by the signal at the intersection.
- (4) When a red light alone is exhibited at an intersection by a traffic control signal,
- (a) a pedestrian facing the red light must not enter the roadway unless instructed that he or she may do so by a pedestrian traffic control signal;
  - (b) except when a left turn permitted by this paragraph is prohibited by a sign at the intersection, the driver of a vehicle facing the red light at the intersection of not more than 2 highways, and in obedience to it is stopped as closely as practicable to a marked crosswalk on the near side of the intersection, or if there is no marked crosswalk, as closely as practicable to the intersection, may cause the vehicle to make a left turn into a highway on which traffic is restricted to the direction in which he or she causes the vehicle to turn, but the driver must yield the right of way to all pedestrians and vehicles lawfully proceeding as directed by the signal at the intersection; and
  - (c) a pedestrian proceeding across the roadway and facing the red light exhibited after he or she entered the roadway
    - (i) must proceed to the sidewalk as quickly as possible, and
    - (ii) has the right of way for that purpose over all vehicles.
- (5) When a red light is exhibited at a place other than an intersection by a traffic control signal,

- (a) the driver of a vehicle approaching the signal must cause it to stop before entering the nearest marked crosswalk in the vicinity of the signal, or if there is no marked crosswalk, then before reaching the signal; and
- (b) a pedestrian may proceed across the roadway.

### **Green arrow**

- 25 (1) When a green arrow is exhibited at an intersection by a traffic control signal,
- (a) the driver of a vehicle facing the green arrow may cause it to enter the intersection and to make only the movement indicated by the green arrow, but must yield the right of way to pedestrians lawfully in the intersection or in an adjacent crosswalk and to other vehicles lawfully in the intersection; and
  - (b) a pedestrian facing the green arrow must not enter the roadway unless a pedestrian traffic control signal or the exhibition of a green light by a traffic control signal instructs the pedestrian that he or she is permitted to do so.
- (2) When a yellow arrow is exhibited at an intersection by a traffic control signal,
- (a) the driver of a vehicle approaching the intersection and facing a yellow arrow must cause the vehicle to stop, unless the stop cannot be made in safety,
    - (i) before entering the marked crosswalk on the near side of the intersection, or
    - (ii) before entering the intersection, if there is no marked crosswalk;
  - (b) the driver of a motor vehicle approaching the intersection and facing the yellow arrow may, when a stop cannot be made in safety, proceed with caution to make the movement indicated by the arrow but must yield the right of way to pedestrians lawfully in the intersection or in an adjacent crosswalk, and to other vehicles lawfully in the intersection;
  - (c) a pedestrian facing the yellow arrow must not enter the roadway; and
  - (d) a pedestrian proceeding across the roadway and facing the yellow arrow exhibited after he or she entered the roadway
    - (i) must proceed to the sidewalk as quickly as possible, and
    - (ii) has the right of way for that purpose over all vehicles.

### **Flashing lights**

- 26 (1) When rapid intermittent flashes of red light are exhibited at an intersection by a traffic control signal,

- (a) the driver of a vehicle approaching the intersection and facing the flashes of red light must cause the vehicle to stop before entering the marked crosswalk on the near side of the intersection, or if there is no marked crosswalk then before entering the intersection, and must not cause the vehicle to proceed until it is safe to do so; and
  - (b) a pedestrian facing the flashes of red light may proceed with caution across the roadway, in a marked or unmarked crosswalk.
- (2) When rapid intermittent flashes of red light are exhibited at a place other than an intersection by a traffic control signal,
  - (a) the driver of a vehicle approaching the signal
    - (i) must cause it to stop before entering the nearest marked crosswalk in the vicinity of the signal, or if there is no marked crosswalk then before reaching the signal, and
    - (ii) may, after having caused the vehicle to stop, cause it to pass the signal and any crosswalk only if conditions of pedestrian traffic in the roadway or any crosswalk in the vicinity of the signal permit it to do so with safety; and
  - (b) a pedestrian may proceed across the roadway.
- (3) When rapid intermittent flashes of yellow light are exhibited at an intersection by a traffic control signal,
  - (a) the driver of a vehicle facing the flashes of yellow light may cause it to enter the intersection and proceed only with caution, but must yield the right of way to pedestrians lawfully in the intersection or an adjacent crosswalk; and
  - (b) a pedestrian facing the flashes of yellow light may proceed with caution across the roadway, in a marked or unmarked crosswalk.
- (4) When rapid intermittent flashes of yellow light are exhibited at a place other than an intersection by a traffic control signal,
  - (a) the driver of a vehicle approaching the signal may cause the vehicle to pass the signal only with caution, and must yield the right of way to pedestrians in the roadway or on any crosswalk in the vicinity of the signal; and
  - (b) a pedestrian may proceed across the roadway with caution.
- (5) When rapid intermittent flashes of green light are exhibited at an intersection or at a place other than an intersection by a traffic control signal,
  - (a) the driver of a vehicle approaching the intersection or signal and facing the signal must cause it to approach the intersection or signal in such a

manner that he or she is able to cause the vehicle to stop before reaching the signal or any crosswalk in the vicinity of the signal if a stop should become necessary, and must yield the right of way to pedestrians lawfully in a crosswalk in the vicinity of the signal or in the intersection; and

- (b) a pedestrian may proceed across the roadway with caution and at an intersection only in a marked or unmarked crosswalk.

### **Stunting**

- 27 A person, whether as a pedestrian, passenger, or driver, and whether or not with the use or aid of any animal, vehicle, or other thing, must not perform or engage in any stunt or other activity on a street that is likely to distract, startle, or interfere with other users of the street.

### **Driving on laned roadway**

- 28 A driver who is driving a vehicle on a laned roadway
  - (a) must not drive it from one lane to another when only a broken line exists between the lanes, unless the driver has ascertained that movement can be made with safety and will in no way affect the travel of another vehicle;
  - (b) must not drive it from one lane to another if that action necessitates crossing a solid line;
  - (c) must not drive it from one lane to another without first signalling his or her intention to do so by hand and arm or approved mechanical device in the manner prescribed by sections 39 and 40;
  - (d) when approaching an intersection intending to turn left must drive the vehicle in the centre lane or in the lane nearest the centre of the roadway on the right hand half of the highway;
  - (e) when approaching an intersection intending to turn right must drive the vehicle in the lane nearest to the right hand side of the roadway;
  - (f) must not pass a vehicle on the left if that action necessitates driving on that part of the highway designated for travel in the opposite direction; and
  - (g) if a traffic control device directs slow moving traffic to use a designated lane, must when driving slowly drive the vehicle in that lane only.

### **Highway lines**

- 29 (1) Despite anything in this Part, if a highway is marked with
  - (a) a solid double line, the driver of a vehicle must drive it to the right of the line only;
  - (b) a double line consisting of a broken line and a solid line,

- (i) the driver of a vehicle proceeding along the highway on the side of the broken line must drive the vehicle to the right of the double line, except when passing an overtaken vehicle, and
  - (ii) the driver of a vehicle proceeding along the highway on the side of the solid line must drive the vehicle to the right of the double line, except only when finishing the passing of an overtaken vehicle; and
  - (c) one single line, broken or solid, the driver of a vehicle must drive the vehicle to the right of the line, except only when passing an overtaken vehicle.
- (2) Subsection (1) (b) (i) and (c) do not apply if a driver is avoiding an obstruction on the highway and first ascertains that the movement can be made with safety and without affecting the travel of any other vehicle.

### **Highway lines exception**

- 30 If the driver of a vehicle is causing the vehicle to enter or leave a highway and the driver has ascertained that he or she might do so with safety and does so without unreasonably affecting the travel of another vehicle, the provisions of sections 28 and 29 are suspended with respect to the driver while the vehicle is entering or leaving the highway.

### **Newly painted lines**

- 31 A person must not drive on or over a newly painted line or marking on a highway when the line is indicated by a traffic control device.

### **Duty when overtaking**

- 32 (1) Except as provided in section 33, the driver of a vehicle overtaking another vehicle
- (a) must cause the vehicle to pass to the left of the other vehicle at a safe distance; and
  - (b) must not cause or permit the vehicle to return to the right side of the highway until safely clear of the overtaken vehicle.
- (2) Except when overtaking and passing on the right is permitted, a driver of an overtaken vehicle,
- (a) on hearing an audible signal given by the driver of the overtaking vehicle, must cause the vehicle to give way to the right in favour of the overtaking vehicle; and
  - (b) must not increase the speed of the vehicle until completely passed by the overtaking vehicle.

**Passing on right**

- 33 (1) The driver of a vehicle must not cause or permit the vehicle to overtake and pass on the right of another vehicle, except
- (a) when the vehicle overtaken is making a left turn or its driver has signaled his or her intention to make a left turn;
  - (b) when on a laned roadway there is one or more than one unobstructed lane on the side of the roadway on which the driver is permitted to drive; or
  - (c) on a one way street or a highway on which traffic is restricted to one direction of movement, where the roadway is free from obstructions and is of sufficient width for 2 or more lanes of moving vehicles.
- (2) Despite subsection (1), a driver of a vehicle must not cause the vehicle to overtake and pass another vehicle on the right
- (a) when the movement cannot be made safely; or
  - (b) by driving the vehicle off the roadway.

**Passing on left**

- 34 A driver of a vehicle must not drive to the left side of the roadway in overtaking and passing another vehicle unless the driver can do so in safety.

**Clear view on passing**

- 35 A driver of a vehicle must not drive to or on the left side of the roadway, other than on a one way highway, unless the driver has a clear view of the roadway for a safe distance, having regard for all the circumstances.

**Divided highways**

- 36 If a highway has been divided into 2 roadways by a physical barrier or clearly indicated dividing section constructed so that it impedes vehicular traffic, a driver must not
- (a) drive a vehicle over, across or within a barrier or dividing section, except at a crossover or intersection; or
  - (b) drive a vehicle on the left hand roadway unless directed or permitted to do so by a police officer or a traffic control device.

**Reverse turn**

- 37 Except as provided by the bylaws of a municipality, a driver must not turn a vehicle so as to proceed in the opposite direction
- (a) unless the driver can do so without interfering with other traffic; or

- (b) when he or she is driving,
  - (i) on a curve,
  - (ii) on an approach to or near the crest of a grade where the vehicle cannot be seen by the driver of another vehicle approaching from either direction within 150 m,
  - (iii) at a place where a sign prohibits making a U-turn,
  - (iv) at an intersection where a traffic control signal has been erected, or
  - (v) in a business district, except at an intersection where no traffic control signal has been erected.

### Signals on turning

- 38 (1) If traffic may be affected by turning a vehicle, a person must not turn it without giving the appropriate signal under sections 39 and 40.
- (2) If a signal of intention to turn right or left is required, a driver must give it continuously for sufficient distance before making the turn in order to warn other traffic.
- (3) If there is an opportunity to give a signal, a driver must not stop or suddenly decrease the speed of a vehicle without first giving the appropriate signal under sections 39 and 40.

### Means of signalling

- 39 (1) Subject to subsection (2), where a signal is required a driver must give it by means of
  - (a) his or her hand and arm,
  - (b) a signal lamp of a type approved under the *Motor Vehicle Act*, or
  - (c) a mechanical device of a type approved under the *Motor Vehicle Act*.
- (2) When a vehicle is constructed or loaded in a manner that makes a signal by hand and arm not visible both to its front and rear, or a body or load extends more than 60 cm to the left of the centre of the steering wheel, a driver must give signals as provided by subclauses (1) (b) or (c), and a person must not drive the motor vehicle on a highway unless it is so equipped.

### Left hand drive signals

- 40 (1) When a driver of a left hand drive vehicle gives a signal by hand and arm, the driver must do so from the left side, and must signify
  - (a) a left turn by extending his or her left hand and arm horizontally from the vehicle;

- (b) a right turn by extending his or her left hand and arm out and upward from the vehicle; and
  - (c) a stop or decrease in speed by extending his or her left hand and arm out and downward from the vehicle.
- (2) A person must not drive a right hand drive vehicle on a highway unless it is equipped with a mechanical or electrical signalling device approved by the Lieutenant Governor in Council.

### **Driving over fire hose**

- 41 Unless he or she has received consent of the fire department official in command or a police officer, a person must not drive a vehicle over an unprotected hose of a fire department when laid down on a highway or private driveway at a fire or an alarm of fire.

### **Driving on sidewalk**

- 42 A driver must not drive on a sidewalk, walkway or boulevard, except when entering or leaving a driveway or lane or when entering or leaving land adjacent to a highway, or by permission granted under a bylaw.

### **Cyclist provisions**

- 43 (1) In addition to the duties imposed by this section, a person operating a cycle on a highway has the same rights and duties as a driver of a vehicle.
- (2) A person operating a cycle
- 26-024 (a) must not, for the purpose of crossing a highway, ride on a crosswalk unless
- (i) authorized to do so by a bylaw,
  - (ii) directed to do so by a sign,
  - (iii) entering or leaving a multi-use trail on a crosswalk linking portions of the trail to one another or to a highway, or
  - (iv) the crosswalk is bordered by, adjacent to, or marked with elephant's feet markings;
- (b) must, subject to paragraph (a), ride as near as practicable to the right side of the highway;
- (c) must not ride abreast of another person operating a cycle on the roadway;
- (d) must keep at least one hand on the handlebars;
- (e) must not ride other than on or astride a regular seat of the cycle;

- (f) must not use the cycle to carry more persons at one time than the number for which it is designed and equipped; and
  - (g) must not ride a cycle on a highway where signs prohibit the cycle's use.
- (3) Nothing in subsection (2)(b) requires a person to ride a cycle on any part of a highway that is not paved.
- (4) A person operating a cycle who intends to turn it to the left at an intersection where there is more than one lane from which left turns are permitted must
- (a) cause the cycle to approach the intersection in the lane closest to the right side of the highway from which a left turn is permitted;
  - (b) keep the cycle to the right of the line that divides the lane referred to in paragraph (a) from the lane immediately to the left of that lane;
  - (c) after entering the intersection, turn the cycle to the left so that it will leave the intersection to the right of the line referred to in paragraph (b); and
  - (d) when practicable, turn the cycle in the portion of the intersection to the left of the centre of the intersection.
- (5) A person must not ride a cycle, skateboard, roller skates, in-line roller skates, sled, play vehicle or other similar means of conveyance when it is attached by the arm and hand of the rider or otherwise to a vehicle on a highway.
- (6) A person must not operate a cycle on a highway without due care and attention or without reasonable consideration for other persons using the highway.

### Skating provisions

- 43A (1) Subject to the applicable provisions of the *Motor Vehicle Act* and its regulations and in addition to the duties imposed by this Bylaw, a person using a skateboard, roller skates, in-line skates, or a non-motorized scooter on a highway has the same rights and duties as a driver of a vehicle.
- (2) A person using a skateboard, roller skates, in-line skates, or a non-motorized scooter on a highway
- (a) must not, for the purpose of crossing a highway, use the device on a crosswalk unless
    - (i) authorized to do so by a bylaw,
    - (ii) directed to do so by a sign, or
    - (iii) entering or leaving a multi-use trail on a crosswalk linking portions of the trail to one another or to a highway,
  - (b) must, subject to section 115(1), use the device as near as practicable to the right side of the highway,

- (c) must not use the device abreast of another person using a cycle, skateboard, roller skates, in-line skates, or a non-motorized scooter on the highway,
  - (d) if the device is a skateboard or non-motorized scooter, must keep at least one foot on the skateboard or non-motorized scooter,
  - (e) must not carry a passenger on the device, and
  - (f) must not use the device on a highway where signs prohibit the device's use.
- (3) Nothing in subsection (2)(b) requires a person to use a skateboard, roller skates, in-line skates, or a non-motorized scooter on any part of a highway that is not paved.
- (4) A person using a skateboard, roller skates, in-line skates, or a non-motorized scooter on a highway who intends to turn left at an intersection where there is more than one lane from which left turns are permitted must
- (a) approach the intersection in the lane closest to the right side of the highway from which a left turn is permitted,
  - (b) keep to the right of the line that divides the lane referred to in paragraph (a) from the lane immediately to the left of that lane,
  - (c) after entering the intersection, turn to the left so that the device will leave the intersection to the right of the line referred to in paragraph (b), and
  - (d) when practicable, turn in the portion of the intersection to the left of the centre of the intersection.
- (5) A person using a skateboard, roller skates, in-line skates, or a non-motorized scooter on a highway between 1/2 hour after sunset and 1/2 hour before sunrise must wear the following equipment:
- (a) a lighted lamp on the person's front and under normal atmospheric conditions capable of displaying a white light visible at least 150 m in the direction the person is pointed;
  - (b) a red reflector of a make or design approved by the Insurance Corporation of British Columbia for the purposes of section 183(6)(b) of the *Motor Vehicle Act*;
  - (c) a lighted lamp, visible to the rear, displaying a red light.
- (6) If an accident occurs by which a person or property is injured, directly or indirectly, owing to the use of a skateboard, roller skates, in-line skates, or a non-motorized scooter on a highway or a sidewalk, the person using the skateboard, roller skates, in-line skates, or a non-motorized scooter must

- (a) remain at or immediately return to the scene of the accident,
  - (b) render all possible assistance, and
  - (c) give to anyone sustaining loss or injury the person's name and address.
- (7) A person must not use a skateboard, roller skates, in-line skates, or a non-motorized scooter on a highway without due care and attention or without reasonable consideration for other persons using the highway.
- (8) A person using a skateboard, roller skates, in-line skates, or a non-motorized scooter on a highway must signify
- (a) a left turn by extending the person's left hand and arm horizontally,
  - (b) a right turn by doing either of the following:
    - (i) extending the person's left hand and arm out and upward so that the upper and lower parts of the arm are at right angles;
    - (ii) extending the person's right hand and arm horizontally, and
  - (c) a stop or decrease in speed by extending the person's left hand and arm out and down.

### **Motorcycles**

- 44 (1) A person operating a motorcycle must ride only astride the regular seat attached to it.
- (2) A person, other than the operator, must not ride on a motorcycle unless
- (a) it is designed and equipped to carry more than one person; and
  - (b) the other person rides
    - (i) astride the permanent and regular seat if designed for 2 persons,
    - (ii) astride another seat firmly attached to the motorcycle behind the seat occupied by the operator; or
    - (iii) on or in another seat firmly attached to one side of the motorcycle.
- (3) A person who is operating a motorcycle must not permit another person to ride on it in violation of subsection (2).
- (4) Except when overtaking and passing other motorcycles, more than 2 operators of motorcycles must not operate their motorcycles side by side in the same direction in the same traffic lane.

### PART 3 - PARKING AND STOPPING

#### Powers of Director of Engineering - parking and stopping zones

- 45 For the purpose of regulating the parking and stopping of vehicles, the Director of Engineering may make orders designating certain streets or portions of streets as any of the following Zones, and designating the following regulations indicated for those Zones:
- (a) Impounding Zones or Tow Away Zones;
  - (b) No Stopping Zone, and the hours during which stopping is prohibited in it;
  - (c) No Parking Zone and the hours during which parking is prohibited in it;
  - (d) Limited Time Parking Zone, and
    - (i) the length of time that a vehicle may be parked continuously in that Zone,
    - (ii) the hours during which the regulations concerning it are in effect, and
    - (iii) the circumstances under which a vehicle may be removed from that Zone when the vehicle is parked in contravention of that Zone's regulations;
  - (e) Residential Parking Zone and the hours during which and the days on which it is in effect;
  - (f) Truck Loading Zone, and the hours during which it is in effect;
  - (g) Hotel Zone;
  - (h) General Loading Zone, and the hours during which it is in effect;
  - (i) School Loading Zone, and
    - (i) the length of time that a vehicle may be continuously parked in that Zone, to a maximum of five minutes, and
    - (ii) for days when school is in session, the hours between 8:00 a.m. and 5:00 p.m., of the same day, during which the regulations concerning that Zone are in effect;
  - (j) Church Loading Zone for the exclusive use of the official vehicles of a funeral procession or wedding party;
  - (k) Accessible Loading Zone or Parking Zone, and
    - (i) the length of time that vehicles may be continuously standing, stopped or parked, and
    - (ii) the hours during which the regulations concerning the Zone are in effect;
  - (l) Taxi Stand for the exclusive use of taxis or a class of taxi;

26-024

- (m) Transit Zone for the exclusive use of transportation buses or a class of transportation bus, or their operators or owners, and the days and the hours during which stopping, standing or parking is prohibited for a vehicle that is not a designated bus;
- (n) Shuttle Bus Zone for the exclusive use of passenger transportation buses for the use of which a fare is not charged, or for any class or type of free bus, or their operators, and the days and the hours during which stopping, standing or parking is prohibited for a vehicle that is not a designated free bus;
- (o) Out of Town Tour Bus Zone only on the south side of the 800 block of Humboldt Street for the exclusive use of transportation buses operating tours starting from outside the City limits, and the months or weeks, the days and the hours during which stopping, standing or parking is prohibited for a vehicle that is not a transportation bus described in this paragraph;

26-024

- (p) Safety Zone for the exclusive use of pedestrians and providing for the erection in that Zone of a platform, curbing or structure that the Director of Engineering considers advisable for the greater convenience or safety of pedestrians;
- (q) Angle Parking Zone within which vehicles must be parked only at an angle with the curb or edge of the roadway;
- (r) Reserved Parking Zone only adjacent to a Federal, Provincial, or Municipal public building, exclusively for the parking of the vehicles of officials and officers engaged in that building, and designating the hours of the day during which that Zone is in effect;
- (s) Special Parking Zone, and the hours and days during which stopping, standing or parking of vehicles is permitted
  - (i) other than in the manner prescribed by section 88(2),
  - (ii) in the manner indicated by the lines, signs, or other markings displayed in that Zone, and
  - (iii) the types of vehicles to which an order made under this paragraph applies;
- (t) No Parking Zone for vehicles over 6 m long, including their load or trailer, except while loading or unloading freight;
- (u) Passenger Zone for the exclusive use of vehicles while engaged in the loading or unloading of passengers;
- (v) Metered Zone, including Small Vehicle Parking Metered Zone, and Pay Station Zone in which parking meters and pay stations, respectively, shall be erected, maintained and operated to collect fees; prescribing the size of spaces within the Small Vehicle Parking Metered Zone; and prescribing fees for the use of parking spaces located in those zones, and the fees may be different in different parts of those zones;

- (w) Ticket Controlled Parking Zone in which ticket dispensers must be erected, maintained, and operated for the purpose of allocating and controlling parking spaces for vehicles, and
  - (i) the fee to be deposited in these ticket dispensers by the drivers of vehicles parked or intended to be parked in these parking spaces, and
  - (ii) the length of time during which a vehicle may be continuously parked within that Zone;
- (x) Sightseeing Stand for the exclusive use of sightseeing vehicles, which designations may differ for different classes or kinds of sightseeing vehicles;
- 26-024 (y) Residential Parking Permit Zone, and the hours and days during which it is restricted to Residential Permit Parking;
- 26-024 24-077 (z) Car Share Co-op Parking Zone for the exclusive use of car share co-op vehicles and stopping, standing or parking in that zone by other vehicles is prohibited, and in which car share EV stations for the exclusive use of electric vehicles that are also car share co-op vehicles may be erected, maintained, and operated, and prescribing fees for the use of car share EV stations in that zone;
- 26-024 (aa) Electric Vehicle Charging Zone in which charging stations for the exclusive use of electric vehicles shall be erected, maintained, and operated, prescribing fees for the use of charging stations and parking spaces in that zone, prescribing the length of time during which a charging station may be utilized or electric vehicle may be continuously parked within that zone, and prohibiting the stopping, standing or parking in that zone by other vehicles;
- 26-024 (bb) Shared Micromobility Parking Zone for the exclusive use of parking or charging shared micromobility devices, and prohibiting the stopping, standing or parking in that zone by other vehicles or devices.

#### **Powers of Director of Engineering - traffic control devices**

- 46 The Director of Engineering may make orders providing for the erection, placing, painting, or marking on a street of a traffic control device that the Director of Engineering considers necessary or expedient to give effect to the provisions of this Bylaw, orders made under this Bylaw, or the provisions of, or orders made under, the *Motor Vehicle Act* and its regulations.

#### **Impounding and tow away zones**

- 47 (1) No person shall park a vehicle in a Tow Away Zone or an Impounding Zone.
- (2) The Director of Engineering or the Police Chief may remove or cause to be removed and impounded a vehicle standing, stopped or parked on the street in a Tow Away Zone or an Impounding Zone.

- (3) The owner of a vehicle removed or impounded under subsection (2) must pay to the City all of the fees, costs and expenses of removal, impoundment and storage of the vehicle before the vehicle will be released to the owner.
- (4) The Director of Engineering may proceed in accordance with the provisions of the *Warehouse Lien Act*, as if the City were a warehouser under that Act, for the sale of a vehicle if any fees, costs, or expenses referred to in subsection (3) are not paid immediately.

### **No stopping zone**

- 48 The driver of a vehicle must not cause or permit it to stop or remain standing in a No Stopping Zone during the hours when stopping is prohibited.

### **No parking zone**

- 49 The driver of a vehicle must not park it or permit it to remain parked in a No Parking Zone during the hours when parking is prohibited.

### **No parking in City lane**

- 50 The driver of a vehicle must not park it or permit it to remain parked at any time in a City lane.

### **Limited time parking zone**

- 51
  - (1) The driver of a vehicle must not park it or permit it to remain parked in a Limited Time Parking Zone for longer than the time during which continuous parking is allowed in accordance with signs placed in or near that Zone.
  - (2) Subsection (1) does not apply to the driver of a vehicle that
    - (a) belongs to the City, its officers, employees, or agents, and
    - (b) is being used in the course of employment of a person referred to in paragraph (a), as evidenced by a sign, marking, or notice that is signed by the Director of Engineering, Corporate Administrator, or Chief of Police and is displayed on the vehicle.
  - (3) The owner of a vehicle that is removed under the direction of the Director of Engineering or the City's Chief of Police from a Limited Time Parking Zone may redeem the vehicle by paying all of the fees, costs, and expenses of removal, detention, and impoundment, including charges for storage.
  - (4) The Director of Engineering may proceed in accordance with the provisions of the *Warehouse Lien Act*, as if the City were a warehouser under that Act, for the sale of a vehicle if any fees, costs, or expenses referred to in subsection (3) are not paid immediately.
  - (5) Subsection (1) does not apply to a person to whom an Employee Parking Exemption Permit for a person with disabilities, or a Parking Exemption

(temporary) Permit for a person with disabilities, has been issued if that permit allows its holder to park in a Limited Time Parking Zone.

- (6) A separate offence is committed at the expiry of each period of time during which a vehicle is illegally parked in a Limited Time Parking Zone in violation of
  - (a) a provision of this section, and
  - (b) signs placed in or near that Zone.
- (7) A person must not do any of the following acts within the time period posted in a City block that is in a Limited Time Parking Zone:
  - (a) move a vehicle from one location to another in the same block;
  - (b) drive a vehicle out of the block and return to the same block.

#### **Limited time parking exemption permit**

- 52 (1) In this section, "permit" means a Limited Time Parking Exemption Permit, substantially in the form shown in subsection (14), as a Restricted Parking Exemption Permit.
- (2) Despite section 51, and subject to the *Motor Vehicle Act* and any other relevant provisions of this Bylaw, a person who holds a valid and subsisting permit and resides within the areas designated as Zones under Parts 1, 2, 3 and 7 of the Zoning Regulation Bylaw may park a passenger vehicle or motorcycle, on which the permit is displayed in accordance with this section, in that portion of a street
  - (a) on which that person's place of residence abuts; and
  - (b) that is included within the area bounded by the extension across the street of the lateral boundaries of the lot on which that person's residence is located.
- (3) A permit must be conspicuously displayed on a parked passenger vehicle or motorcycle in a manner that allows the permit to be readily observed and read by persons standing adjacent to the passenger vehicle or motorcycle.
- (4) A person may from time to time apply in writing to the Director of Engineering for a permit if that person
  - (a) does not have off-street parking at that person's residence; and
  - (b) resides within any of the designated areas referred to in subsection (2) in
    - (i) a single family dwelling, or a duplex, as defined in the Zoning Regulation Bylaw, that was built before 1956, or
    - (ii) a building that contains 3 self-contained dwelling units and was built before 1985.

- (5) The Director of Engineering may issue a permit after considering the space available for parking on the street to which the permit applies.
- (6) The Director of Engineering may revoke or refuse to renew a permit if for any reason the space available for residential parking is reduced on the street to which the permit applies or would apply.
- (7) A permit that has not been revoked sooner or renewed is valid for one year.
- (8) A permit holder may renew a permit by applying in writing to the Director of Engineering.
- (9) If a permit holder ceases to be a resident of the place of residence shown on the permit, the permit expires immediately.
- (10) A person must not hold more than one subsisting permit.
- (11) The Director of Engineering may revoke the permit of a person who has obtained it by supplying false information.
- (12) A permit must not be issued for a residence while another permit is in effect for that residence.
- (13) The Director of Engineering may issue a replacement permit to a person who has lost or destroyed a permit if that person produces reasonable evidence of the loss or destruction.
- (14) A permit must be substantially in the following form:

"RESTRICTED PARKING EXEMPTION PERMIT

Holder:

Place of Residence (street address)

Date of Issue:                      Renewed:

This vehicle may be parked on the street abutting the residence at the above address, in the manner required by section 52 of the Streets and Traffic Bylaw, at any time and for periods in excess of the time limit shown on signs posted on that street under the Bylaw. This permit expires one year from the date of its issuance or last renewal and may be renewed on application to the Director of Engineering."

- (15) This section does not exempt a person from any other provision of this Bylaw or the *Motor Vehicle Act* in connection with the parking and stopping of vehicles.

### **Residential parking zone**

- 53 (1) The driver of a vehicle may park it or permit it to remain parked on the street in a Residential Parking Zone if, in relation to a dwelling located on a City block abutting that Zone, the driver:

- (a) resides there;
  - (b) is visiting an occupant there; or
  - (c) is transacting business, performing work, or rendering services there.
- (2) Despite subsection (1), if only one side of a street is designated a Residential Parking Zone for a City block or part of a City block, a driver of a vehicle may park the vehicle or permit it to remain parked on that side of the street for any one or more of the purposes described in subsection (1) in relation to a dwelling if the dwelling is located on a lot that
- (a) abuts a No Stopping Zone or a No Parking Zone that is on the other side of the street,
  - (b) is located on that City block,
  - (c) is located on the other side of the street directly across from the Residential Parking Zone, and
  - (d) is zoned, under the Zoning Regulation Bylaw or Zoning Bylaw 2018, for single family dwelling or duplex use.

#### **Residential parking permit zone**

- 54 (1) The driver of a passenger vehicle or motorcycle may park it or permit it to remain parked in a designated Residential Parking Permit Zone during the hours when it is in effect for a particular City block or portion of a City block only if a valid permit issued under this section is displayed in or on the vehicle or motorcycle.
- (2) A residential parking permit must be conspicuously displayed on a parked passenger vehicle or motorcycle in a manner that allows the permit to be readily observed and read by persons standing adjacent to the passenger vehicle or motorcycle.
- (3) A person who resides at a dwelling that is located on a lot in a Residential Parking Permit Zone may apply in writing to the Director of Engineering for a permit.
- (4) The Director of Engineering may issue a permit
- (a) after considering the space available for parking on the street to which the permit applies, and
  - (b) upon payment of an annual fee of \$20.00.
- (5) The Director of Engineering may revoke or refuse to renew a permit if for any reason the space available for residential parking is reduced on the street to which the permit applies or would apply.
- (6) A permit that has not been revoked sooner or renewed is valid for one year.

- (7) A permit holder may renew a permit by applying in writing to the Director of Engineering.
- (8) If a permit holder ceases to be a resident of the place of residence shown on the permit, the permit expires immediately.
- (9) A person must not hold more than 2 subsisting permits.
- (10) The Director of Engineering may revoke the permit of a person who has obtained it by supplying false information.
- (11) The Director of Engineering may issue a replacement permit to a person who has lost or destroyed a permit if that person produces reasonable evidence of the loss or destruction.
- (12) This section does not exempt a person from any other provision of this Bylaw or the *Motor Vehicle Act* in connection with the parking and stopping of a vehicle.

### **Truck loading zone**

- 55 (1) Subsection (2) does not apply to either of the following vehicles:
- (a) a commercial vehicle from which goods, wares or merchandise are actually being loaded or unloaded;
  - (b) a Canada Post Corporation vehicle into which mail is actually being loaded from a receptacle that is located on a street and authorized by Canada Post Corporation for the posting of mail.
- (2) The driver of a vehicle must not cause or permit it to stop or remain standing in a Truck Loading Zone during the hours the Zone is in effect.
- (3) The driver of a vehicle described in subsection (1) must not cause or permit it to stop or remain standing in a Truck Loading Zone for longer than one half hour when the Zone is in effect.
- (4) A separate offence is committed at the expiry of each half hour during which a vehicle is parked in a Truck Loading Zone in violation of a provision of this section.

24-024

### **Hotel zone**

- 56 (1) Subject to subsections (2) to (5), the driver of a vehicle may cause or permit it to stop or remain standing in a Hotel Zone
- (a) for not more than 10 minutes, and
  - (b) only if the vehicle is being used by a person who is leaving or entering the hotel building immediately adjacent to the Hotel Zone.
- (2) The Director of Engineering may issue a Hotel Zone permit to a person with a sightseeing vehicle.

- (3) A Hotel Zone permit authorizes a sightseeing vehicle to park in a Hotel Zone that is designated in the permit.
- (4) A permit issued under this section is valid for 6 months from the date it is issued.
- (5) A permit issued under this section must be displayed on the vehicle for which it is issued in a manner that allows the permit to be readily visible from outside the vehicle.

### **General loading zone**

- 57 (1) The driver of a vehicle may cause or permit it to stop or remain standing in a General Loading Zone, during the hours the Zone is in effect, only for a period not exceeding
  - (a) 3 minutes for the purpose of loading or unloading passengers, or
  - (b) 15 minutes while goods or merchandise are actually being loaded or unloaded from the vehicle.
- (2) A separate offence is committed at the expiry of each 15 minutes during which a vehicle is parked in a General Loading Zone in violation of this section.

### **School loading zone**

- 58 The driver of a vehicle must not park it or permit it to remain parked in a School Loading Zone for longer than the time during which continuous parking is allowed in accordance with signs placed in or near that Zone.

### **Church loading zone**

- 59 The driver of a vehicle that is not an official vehicle of a funeral procession or wedding party, must not park the vehicle or permit it to remain parked within a Church Loading Zone that is designated for the exclusive use of those official vehicles.

### **Parking and loading zones for persons with disabilities**

- 60 (1) The driver of a vehicle must not cause or permit the vehicle to park, stop or remain standing in a Loading Zone for persons with disabilities when the Zone is in effect, except for the purpose of loading or unloading disabled passengers.
- (2) For the purposes of this section,
  - (a) “designated authority” means the Victoria Resource Centre for Independent Living as organizations entitled to issue an accessible parking permit on being satisfied with an application in the manner prescribed by Division 38 of the Regulations referred to in subsection(2)(b);
  - (b) “accessible parking permit “ means a permit in the form prescribed by Division 38 of the Motor Vehicle Act Regulations, B.C. Reg 26/58, issued by a designated authority or a placard, permit, decal or licence plate

issued for the same purpose by an authority having jurisdiction elsewhere in British Columbia or Canada or in another country;

(c) “permitted driver” means the driver of a vehicle who is the valid holder of and displays an accessible parking permit in the vehicle by

(i) suspending it from the rearview mirror inside the vehicle so that it is in plain view of any person looking through the windshield of the vehicle from the sidewalk or roadside, or

(ii) by placing it on the dashboard in front of the driver's position.

(3) No person, other than a permitted driver, may park or stop a vehicle, or cause or permit it to remain standing, in a Parking Zone for persons with disabilities.

(4) A permitted driver must not park a vehicle in a Parking Zone for persons with disabilities for longer than the time during which a vehicle may be continuously parked in that Zone in accordance with signs placed in or near that Zone.

### **Taxi stand**

61 (1) The driver of a vehicle that is not a taxi must not cause or permit it to stop or remain standing in an area designated as a taxi stand.

(2) Taxi drivers in a taxi stand must:

(a) arrange their taxis and load passengers into the taxis in the successive chronological order in which the taxis arrived in the taxi stand, with the taxis that arrive earliest placed nearest the front of the taxi stand; and

(b) drive forward in succession to occupy areas vacated by taxis that leave the taxi stand.

(3) If a taxi from one company enters a taxi stand after 2 or more taxis from another company, the drivers of the taxis from that other company, except the driver that was earliest in the taxi stand, must leave it.

4) When a taxi is stopped in a taxi stand and the taxi's driver is not loading, unloading or assisting passengers, the driver must

(a) remain with the taxi, and

(b) keep the taxi's doors closed.

### **Transit zone**

26-024 62 The driver of a vehicle must not cause or permit that vehicle to stop or remain standing in a Transit Zone during the times when the Zone is in effect unless the vehicle is

(a) a transportation bus of a class for which the exclusive use of an area has been designated as a Transit Zone;

- (b) a vehicle belonging to an operator for whom an area has been designated as a Transit Zone.

### **Shuttle bus zone**

- 63 The driver of a vehicle must not cause or permit the vehicle to stop or remain standing in a Shuttle Bus Zone during the times when the Zone is in effect unless the vehicle is
- (a) a transportation bus of a class for which the exclusive use of an area has been designated as a Shuttle Bus Zone;
  - (b) a vehicle belonging to an operator for whom an area has been designated as a Shuttle Bus Zone.

### **Out of town tour bus zone**

- 64 The driver of a vehicle that is not a transportation bus, for which an area is designated as an Out of Town Tour Bus Zone, must not cause or permit the vehicle to stop or remain standing within that Zone during the times when the Zone is in effect.

### **Safety zone**

- 65 The driver of a vehicle must not cause or permit it to proceed into or be in a Safety Zone.

### **Angle parking**

- 66
- (1) The driver of a vehicle must park it within an Angle Parking Zone to stand within 30 cm of, and at an angle with, the curb, as indicated by the lines that mark that Zone.
  - (2) The driver of a vehicle that is longer than 6 m must not park it in an Angle Parking Zone.
  - (3) The driver of a vehicle must park it in a space in an Angle Parking Zone so that the curb or edge of the roadway is at the forward end of the vehicle.

### **Reserved parking area**

- 67 The driver of a vehicle that is not for the use of an official or officer referred to in section 45(r) must not park the vehicle or permit it to remain parked in a Reserved Parking Area during the times that it is in effect.

### **Special parking zone**

- 68 The driver of a vehicle must not park the vehicle in a Special Parking Zone contrary to the regulations under this bylaw posted in that Zone.

### **No parking (vehicles over 6m) zone**

- 69 The driver of a vehicle over 6 meters long must not park the vehicle in a No Parking (Vehicles over 6m) Zone except for the purpose of loading or unloading freight.

### **Passenger zone**

- 70 (1) The driver of a vehicle must not cause or permit it to stop or remain standing in a Passenger Zone for
- (a) longer than 3 minutes, and
  - (b) any purpose other than loading and unloading passengers.
- (2) A separate offence is committed at the expiry of each 15 minutes that a vehicle is stopped or parked in a Passenger Zone in violation of this section.
- (3) Subject to subsection (4), the driver of a single horsedrawn sightseeing vehicle may park in a Passenger Zone on the west side of Menzies Street between Belleville and Quebec Streets.
- (4) The driver of a single horsedrawn sightseeing vehicle parked in a Passenger Zone described in subsection (3) must yield to a motor vehicle that requires the use of that Zone.

### **Parking meter zone**

- 71 (1) The driver of a vehicle must not park the vehicle or permit it to remain parked on a portion of a street in a Metered Zone or a Pay Station Zone except within a Parking Space.
- (2) The driver of a vehicle parked in a metered space must immediately deposit in the appropriate meter a fee for parking in the manner and in accordance with the rate prescribed and measured by the meter.
- (3) When the information displayed in a parking meter head indicates that there is no time left within which a vehicle may be parked in a metered space, the driver of the vehicle may park it in that space only for the purpose of depositing, and for as long as is reasonably necessary for the driver to deposit, the required fee.
- (4) A driver must not cause or permit a vehicle to remain parked in a metered space longer than the time during which a vehicle may be continuously parked within the space as indicated on the parking meter or by a sign.
- (5) A separate offence is committed at the expiry of each maximum period of time during which a vehicle is illegally parked in a Metered Zone in violation of
- (a) a provision of this section, and
  - (b) signs placed in or near that Zone.
- (6) The driver of a vehicle must park the vehicle in a metered space, marked to indicate angle parking, in a manner that places the front of the vehicle next to the parking meter.
- (7) The driver of a vehicle must not park it within a metered space that is occupied by another validly parked vehicle.

- (8) The vehicle closest to the parking meter for a metered space is the only vehicle that is considered to be validly parked when 2 or more vehicles are parked in that metered space at the same time.
- (9) Despite subsections (7) and (8), 2 motorcycles may validly park in one metered space.
- (10) Subject to any special regulation that is made under this Bylaw and is indicated by a sign at or near a metered space
- (a) subsections (2), (3) and (4) do not apply on:
- (i) holidays other than Sundays,
- (ii) days other than holidays between 8:00 p.m. of one day and 8:00 a.m. of the next day, and
- (iii) Sundays between 8:00 p.m. and 8:00 a.m. of the following Monday.
- (b) Despite subsection (10)(a)(i), subsections (2) and (3) do not apply on Sundays to a permitted driver as defined in section 60.
- (11) Subsections (2), (3) and (4) do not apply to the driver of a vehicle belonging to any of the following classes:
- (a) a vehicle that belongs to the City, its officers, employees, or agents, and that is being used in the course of that person's employment, as indicated by
- (i) a sign or marking, or
- (ii) a notice signed by the Director of Engineering, Corporate Administrator, or Chief of Police, and displayed on the vehicle;
- (b) a vehicle that belongs to, and is being used to transport the Mayor, a City Councillor, a member of Parliament, or a Member of the Legislative Assembly, as indicated by a notice signed by the Director of Engineering or Chief of Police, and displayed on the vehicle;
- (c) a vehicle being used by the Canadian Armed Forces, or by a public utility, and designated as an emergency vehicle by the Director of Engineering;
- (d) an ambulance, or a vehicle being used by an organized Fire Department or Police Department;
- (e) a vehicle bearing the flag or insignia of the Lieutenant Governor of British Columbia or of the Senior Officer commanding the Canadian Armed Forces on Vancouver Island.
- (12) The following requirements apply to a Small Vehicle Parking Metered Zone that is not more than 3 m long:

BL 23-045

- (a) the Zone may be used only by vehicles that are less than 3 m long, including but not limited to motorcycles, mopeds, scooters, and automobiles;
- (b) a vehicle must be parked parallel to the curb unless otherwise indicated by sign or street markings.

### **Pay Station Zone**

- 72
- (1) A person who parks in a parking space in a Pay Station Zone must immediately pay the parking fee for that space and the desired time at the nearest pay station by any method indicated in the instructions on the pay station.
  - (2)
    - (a) No person shall park in a parking space within a Pay Station Zone for any longer than the amount of time purchased for that space.
    - (b) Subsection (a) does not apply to the act of parking or to the necessary time to pay the parking fee at the nearest parking pay station.
  - (3) Despite any amount paid, no person shall park in any parking space within a Pay Station Zone for any longer than the limited period of time for which parking is lawfully permitted as stated in the legend on the parking space or the parking pay station.
  - (4) No person shall park in a Pay Station Zone except within a parking space.
  - (5) The exemptions for parking in sections 71(10) and (11) apply in Pay Station Zones to parking by
    - (a) all persons during the days and times set out in section 71(10), and
    - (b) the classes listed in subsections 71(11)(a) to (e), both inclusive, under the same terms and conditions set out in section 71(11) as applicable to those classes.
  - (6) the exemptions granted under section 73 to a person with disabilities who holds a valid and subsisting Employee Accessible Parking Permit, an Accessible Parking (Temporary) Permit or an Accessible Parking Permit are applicable to that holder when parking in Pay Station Zones under the same terms and conditions applicable to the holder under section 73.
  - (7) No person shall park a vehicle within a parking space in a Pay Station Zone already occupied by another vehicle.
  - (8) If more than one vehicle is parked in a parking space in a Pay Station Zone, the vehicle parked in the manner directed by section 86 and nearest to the delineated forward end of the parking space is deemed to be validly parked and any other vehicle parked in that parking space is deemed to be unlawfully parked.

- (9) Despite subsections (7) and (8), two motorcycles may validly park in one parking space in a Pay Station Zone.
- (10) If a person parks a vehicle contrary to the provisions of this section, a separate offence is deemed to have been committed for each successive period of time during which the vehicle could have been lawfully parked during the period of time the vehicle was unlawfully parked in the parking space.

### **Electric Vehicle Charging Zone**

- 72A
- (1) The driver of an electric vehicle must not cause or permit the electric vehicle to park, stop or remain standing in an Electric Vehicle Charging Zone when the Zone is in effect, except for the purpose of charging the electric vehicle at a charging station for the permitted time in accordance with signs placed in or near that Zone.
  - (2) The driver of a vehicle that is not an electric vehicle must not cause or permit the vehicle to stop or remain standing within an area designated as an Electric Vehicle Charging Zone during the times when the Zone is in effect.
  - (3) The driver of an electric vehicle must immediately upon parking, connect the electric vehicle to the charging station closest to the parking space at which the electric vehicle is parked to initiate a charging session, and pay the fee for that space and charging time at the end of the session by any method indicated in the instructions on the charging station.
  - (4) No person shall use a charging station for any longer than
    - (a) the amount of time purchased for that space; and
    - (b) the limited period of time for which charging is lawfully permitted as stated on the charging station or posted sign.
  - (5) No person shall tamper with, deface, damage, or destroy a charging station.
  - (6) No person shall plug or unplug an electric vehicle not under their custody from a charging station.
  - (7) If a person parks or charges a vehicle contrary to the provisions of this section, a separate offence is deemed to have been committed for each successive period of time during which the vehicle could have been lawfully parked during the period of time the vehicle was unlawfully parked in the parking space.

24-077

### **Car Share Co-op Parking Zone**

- 72B
- (1) In a Car Share Co-op Parking Zone when the Zone is in effect, the driver of a vehicle must not:
    - (a) cause or permit the vehicle to stop or remain standing unless the vehicle is a car share co-op vehicle, or

- (b) cause or permit the vehicle to stop or remain standing within a parking space designated for the use of a car share EV station, except for the purpose of charging an electric vehicle that is a car share co-op vehicle at a charging station for the permitted time in accordance with signs placed in or near that Zone.
- (2) The driver of an electric vehicle must immediately upon parking, connect the electric vehicle to the car share EV station closest to the parking space at which the electric vehicle is parked to initiate a charging session.
- (3) No person shall tamper with, deface, damage, or destroy a car share EV station.
- (4) If a person parks or charges a vehicle contrary to the provisions of this section, a separate offence is deemed to have been committed for each successive period of time during which the vehicle could have been lawfully parked during the period of time the vehicle was unlawfully parked in the parking space.

**26-024 Shared Micromobility Parking Zone**

- 72C
- (1) No person shall place, park or stand a shared micromobility device in any location other than in an upright position within the marked boundaries of a Shared Micromobility Parking Zone.
  - (2) No person shall tamper with, deface, damage or destroy a shared micromobility device in any location, a shared micromobility charging station, or any other infrastructure or signage within a Shared Micromobility Parking Zone.
  - (3) No person shall park or charge any vehicle or device other than a shared micromobility device in a Shared Micromobility Parking Zone.
  - (4) If a person parks or charges a vehicle or device contrary to the provisions of this section, a separate offence is deemed to have been committed for each successive period of time during which the vehicle or device could have been lawfully parked during the period of time the vehicle or device was unlawfully parked in the Shared Micromobility Parking Zone.

**Parking exemption permits for persons with disabilities**

- 73
- (1) Subsections 71(2), (3) and (4) and 72(1), (2) and (3) do not apply to a person who is
    - (a) the holder of a valid and subsisting Employee Parking Exemption Permit for persons with disabilities or Parking Exemption (Temporary) Permit for persons with disabilities, or
    - (b) the holder of, or the driver of a holder of, a valid and subsisting Parking Exemption Permit for persons with disabilities.
  - (2) A person with disabilities who is employed in an area of the City in which Metered Zones are designated may apply to the Director of Engineering for an Employee Parking Exemption Permit for persons with disabilities and must

- (a) deliver with this application a letter from that person's employer stating the employee's need for convenient parking and access to that person's place of employment,
  - (b) possess a person with disabilities parking permit issued by a designated authority as defined in section 60, and
  - (c) pay an annual permit fee of \$60.00 per month for a one-year, all-day parking permit.
- (3) The Director of Engineering must issue an Employee Parking Exemption Permit for persons with disabilities when satisfied that an applicant has complied with subsection (2).
- (4) An Employee Parking Exemption Permit for person with disabilities issued under subsection (3)
  - (a) is valid for one year from the date on which it is issued,
  - (b) is valid only for the person to whom it is issued, and
  - (c) entitles its holder to park, without payment of a parking fee, in a parking space in a Parking Meter Zone or Pay Station Zone for which the parking time is not limited to 20 minutes.
- (5) A person with disabilities who is physically incapable of operating a parking meter may apply to the Director of Engineering for a Parking Exemption Permit for persons with disabilities and must:
  - (a) possess a person with disabilities parking placard of the Social Planning and Research Council of British Columbia (SPARCBC), issued by the Victoria Resource Centre for Independent Living, and
  - (b) pay an annual fee of \$20.00 for a one-year, two-hour limit parking permit for each location of parking up to a maximum of 2 continuous hours.
- (6) The Director of Engineering must issue a Parking Exemption Permit for persons with disabilities when satisfied that an applicant has complied with subsection (5).
- (7) A Parking Exemption Permit for persons with disabilities issued under subsection (6):
  - (a) is valid for one year from the date on which it is issued,
  - (b) is valid only for the person to whom it is issued, and
  - (c) entitles the holder of the permit or the driver of the vehicle in which the holder of the permit is a passenger, to park for up to 2 continuous hours, without payment of a meter fee, in a metered space for which the parking time is not limited to 20 minutes.

- (8) The driver of a vehicle must not display in that vehicle a Parking Exemption Permit for persons with disabilities at a time when the driver is not in the course of providing transportation to the person with disabilities to whom the permit is issued.
- (9) A person with disabilities may apply to the Director of Engineering for a Parking Exemption (Temporary) Permit for persons with disabilities and
  - (a) when required, must deliver with this application a medical doctor's certificate that verifies the temporary disability, and
  - (b) must pay any of the following permit fees:
    - (i) \$20.00 for a seven-day, all-day parking permit;
    - (ii) \$4.00 for one all-day parking permit.
- (10) The Director of Engineering must issue a Parking Exemption (Temporary) Permit for persons with disabilities when satisfied that an applicant has complied with subsection (9).
- (11) A Parking Exemption (Temporary) Permit for persons with disabilities issued under subsection (10)
  - (a) is valid for the period indicated on the permit,
  - (b) is valid only for the person to whom it is issued, and
  - (c) entitles its holder to park, without payment of a meter fee, in a metered space for which the parking time is not limited to 20 minutes.
- (12) A permit issued under this section must be in a form that is approved and signed by the Director of Engineering.

24-046

### **Passenger Directed Vehicle in Metered or Pay Station Zones**

BL 23-054

- 74 The driver of a passenger directed vehicle may stand it in a parking space in a Metered Zone or Pay Station Zone without charge for no longer than 2 minutes for the purpose of loading and unloading passengers.

### **Trailers in Metered or Pay Station Zones**

- 75 The driver of a vehicle must not cause or permit it to be parked in a parking space in a Metered Zone or Pay Station Zone if the vehicle has a trailer attached to it.

### **Temporary discontinuance and reservation of parking spaces in a Metered or Pay Station Zone**

- 76 (1) The Director of Engineering by order may

- (a) temporarily discontinue the use of parking spaces in Metered or Parking Pay Station Zones, and
  - (b) cause the placement of temporary signs that prohibit parking in parking spaces that are temporarily discontinued.
- (2) The driver of a vehicle must not park in a parking space while its use has been discontinued under this section.
- (3) The Director of Engineering, by order, may reserve one or more parking spaces for the use of persons carrying out a special purpose or construction, repair, demolition, or other work in or near a Metered or Parking Pay Station Zone.
- (4) A person for whom the Director of Engineering reserves a parking space for commercial use must pay a fee of \$20.00 per day or \$2,000.00 per year.
- (5) The driver of a vehicle must not park in a parking space that has been reserved under subsection (3) for another person.

#### **Exemption for car share vehicles**

76A (1) In this section:

“Car Share Organization”

means an organization which owns ten or more vehicles for the purpose of shared use among its members

“Free Floating Vehicle”

means a vehicle owned by a Car Share Organization which is shared among the organization’s members and has no fixed or dedicated public parking space.

- (2) A Car Share Organization may apply to the Director of Engineering for an annual exemption from payment at metered or parking pay station zones within the City by submitting an application in the form prescribed by the Director of Engineering.
- (3) Upon receipt of the following from a Car Share Organization
  - (a) an application under subsection (2) and
  - (b) a payment of \$2,000 for each of its Free Floating Vehicle used within the City,

the Director of Engineering may issue an annual exemption from payment at metered or parking pay station zones to that Car Share Organization.
- (4) Sections 71(2) to (4) and 72(1) and (2) of this bylaw, do not apply to the driver of

a Free Floating Vehicle provided that:

- (a) the Free Floating Vehicle is owned by a Car Share Organization that holds a valid permit issued under subsection (3); and
- (b) the Free Floating Vehicle is clearly identified as being owned and operated by the Car Share Organization that holds a valid permit under subsection (3).

### **Lawful coins required in parking meter and pay station**

- 77 A person must not insert in a parking meter or pay station any object that is not a lawful coin of Canada or the United States of America.

### **Ticket controlled parking zones**

- 78 (1) Subsection (2) applies only when a ticket dispenser is in effect in a Ticket Controlled Parking Zone in accordance with a sign that is displayed, by the order of the Director of Engineering, in that Zone in the vicinity of the dispenser.
- (2) The driver of a vehicle may cause or permit it to be parked or remain parked in a parking space in a Ticket Controlled Parking Zone only if the driver has
- (a) deposited coins in the ticket dispenser for that Zone, in the amount and manner indicated on the sign described in subsection (1),
  - (b) obtained the tickets issued by the dispenser, and
  - (c) displayed the tickets on the dash of the vehicle in a manner that permits the tickets to be readily observed and read from outside the vehicle.
- (3) The driver of a vehicle may park it or cause or permit it to remain parked in Ticket Controlled Parking Zone only if the vehicle is within a parking space that is marked under an order made under this Bylaw.
- (4) The driver of a vehicle must not insert or deposit in a ticket dispenser any object that is not a lawful coin of Canada or the United States of America.
- (5) Despite any provision of this or any other Bylaw, for the purposes of this Bylaw a parking facility is in a Ticket Controlled Parking Zone
- (a) when a ticket dispenser is in operation in or on that parking facility,
  - (b) whether the parking facility is outdoors or within a structure, and
  - (c) when the parking facility is owned or operated by or on behalf of the City.
- (6) The driver of a vehicle may park it in a parking space that is within a Ticket Controlled Parking Zone clearly designated as reserved for parking for persons with disabilities only if that driver has clearly displayed in or on the vehicle

- (a) An accessible parking placard of the Social Planning and Research Council of British Columbia, issued by the Victoria Resource Centre for Independent Living, or
  - (b) a similar placard, permit, decal or licence plate issued by another jurisdiction having another jurisdiction having authority to do so.
- (7) The driver of a vehicle must not park it or cause or permit it to remain parked in a Ticket Controlled Parking Zone longer than the time during which vehicles may be continuously parked in that Zone, as indicated by signs placed in or near that Zone.

### **Sightseeing vehicle stands**

- 79 A person must not cause or permit a vehicle to stop or remain in a Sightseeing Stand if that vehicle is not a sightseeing vehicle licensed under the Vehicles For Hire Bylaw.

### **Reserved stand for horsedrawn sightseeing vehicles**

- 80 A person must not park or stop a vehicle in a Horsedrawn Sightseeing Stand if that vehicle is not a horsedrawn sightseeing vehicle licensed under the Vehicles For Hire Bylaw.

### **26-024 [Repealed]**

- 81 [repealed]

### **Vehicle standing while loading or unloading freight**

- 82 (1) This section does not apply in an Angle Parking Zone.
- (2) The driver of a vehicle may permit it to stand in a street in a manner other than prescribed in section 88(2) while the driver of a vehicle is loading or unloading merchandise or freight,
- (a) unless otherwise provided by an order of the Director of Engineering, and
  - (b) at any time
    - (i) on a holiday,
    - (ii) between 7:30 a.m. and 6:00 p.m. of a day other than a holiday, or
    - (iii) designated by the Director of Engineering.
- (3) The driver of a vehicle that is standing as provided in this section must ensure that the vehicle is
- (a) within a 30 degree angle with the curb, and
  - (b) not farther than 30 cm from the curb at its nearest point to the vehicle.

**Night parking**

- 26-024 83 (1) (1) A person must not park a semi-trailer on a street between 10:00 p.m. of one day and 6:00 a.m. of the next day.
- (2) A vehicle that is
- (a) a motor home,
  - (b) a camper truck,
  - (c) a trailer used for recreational purposes,
  - (d) a pleasure boat and trailer used for recreational purposes; or
  - (e) a trailer that is in excess of:
    - (i) 1400 kg., registered GVW, or
    - (ii) 6 metres in length,
- and that is registered to, or owned by, a person with an address within the Capital Regional District must not be parked on any street between 10:00 p.m. of one day and 6:00 a.m. of the next day.

**Sleeping in vehicles**

- 84 (1) A person must not park a vehicle in a street for the purpose of sleeping overnight in the vehicle.
- (2) A person must not sleep overnight in a vehicle parked on a street.

**Distance between parked vehicles**

- 85 The driver of a vehicle must not cause or permit it to be parked closer than 1 m to another vehicle if those vehicles are parked parallel to the edge of a roadway.

**Parking on one way street**

- 86 (1) The driver of a vehicle may stop, stand or park the vehicle on the left side of the roadway on a one way street if that is not otherwise prohibited.
- (2) The driver of the vehicle parked as described in subsection (1) must ensure that the wheels of the vehicle are
- (a) parallel to the left side of the roadway on which the vehicle is parked, and
  - (b) within 30 cm of the curb, if there is a curb.

**Miscellaneous stopping, standing, parking**

- 87 (1) Subsection (2) does not apply when the stopping, standing or parking of a vehicle is necessary
- (a) to avoid conflict with traffic, or
  - (b) to comply with the directions of a police officer or a traffic control device.
- (2) A person must not stop, stand or park a vehicle in a manner or location described below:
- (a) subject to section 111, on a sidewalk or boulevard;
  - (b) in front of a public or private driveway crossing;
  - (c) within 1.5 m of either side of a public or private driveway crossing, as measured from the inside edge of the flared portion of the driveway;
  - (d) in any intersection unless permitted by a sign;
  - (e) within 5 m of a fire hydrant, measured from a point on the curb or edge of the roadway which is closest to the fire hydrant;
  - (f) on any crosswalk;
  - (g) within 6 m of the approach side of any crosswalk;
  - (h) within 6 m upon the approach to a flashing beacon, stop sign, or traffic control signal located at the side of a roadway;
  - (i) within 15 m of the nearest rail of a railway crossing;
  - (j) on a highway for any period in excess of 72 consecutive hours;
  - (k) on a highway for the principal purpose of:
    - (i) displaying a vehicle for sale,
    - (iii) advertising, greasing, painting, wrecking, storing, or repairing a vehicle unless an emergency makes repairs necessary,
    - (ii) displaying a sign, or
    - (iii) selling flowers, fruit, vegetables, seafood, or any other commodity;
  - (l) alongside or opposite a street excavation or obstruction when the stopping, standing, or parking obstructs traffic;
  - (m) on the roadway side of a vehicle stopped or parked at the edge or curb of a roadway;

- (n) on a bridge or other elevated structure on a highway except where the stopping, standing, or parking is permitted by a traffic control device;
  - (o) in a place where a traffic control device that gives notice that stopping, standing or parking is prohibited or restricted;
  - (p) in a manner that obstructs the visibility of a standard traffic sign erected by or with the authority of the provincial minister responsible for highways, or under the authority of this Bylaw.
- (3) Despite subsection (2)(j)(iv), a mobile bicycle vendor is permitted to sell products as defined and under the conditions specified in Schedule I.
- 87A (1) The Director may designate an area at or near a fire hydrant as a taxi stand and may cause a sign indicating that the area can be used by taxi cabs to be erected at or near such fire hydrant.
- (2) Notwithstanding section 87(2)(d), a licenced taxi may stop, stand or park as directed by the sign erected pursuant to subsection (1), provided the driver remains in the vehicle at all times.
- (3) A taxi driver must remove the taxi cab from the area designated under subsection (1) if directed to do so by a police officer, a firefighter or in the event of an emergency requiring the use of the fire hydrant.

### **Curb parking**

- 88 (1) Subsection (2) does not apply on a street or portion of a street
- (a) within an Angle Parking Zone, or
  - (b) where stopping, standing or parking is permitted under subsections 45(s) or 88(2), or section 86.
- (2) A driver must not stop, stand, or park a vehicle on a roadway other than on the right side of the roadway and with the right hand wheels
- (a) parallel to that side, and
  - (b) if there is a curb on that side, within 30 cm of the curb.

### **Stopping at intersections**

- 89 (1) Subsection (2) does not apply when a police officer directs a driver otherwise than as prescribed in subsection (2).
- (2) If there is a stop sign at an intersection, the driver of a vehicle must stop
- (a) if there is a marked stop line, at that line;
  - (b) before entering a marked crosswalk on the near side of the intersection;

- (c) if there is neither a marked crosswalk nor a stop line, before entering the intersection, at the point nearest the intersecting highway from which the driver has a view of approaching traffic on the intersecting highway.

#### **Yellow curb lines**

- 90 (1) Subject to an order made under section 45, a person may stop, park, or leave standing an attended or unattended motor vehicle adjacent to a portion of a curb painted yellow, only when that is necessary
  - (a) to avoid conflict with other traffic, or
  - (b) to comply with the direction of a police officer.
- (2) Despite subsection (1) a mobile bicycle vendor may stop on a yellow curb within 6 metres of a legal parking or loading space for up to 60 minutes, unless otherwise restricted by a traffic order under this Bylaw.

### **PART 4 - VEHICLE SIZE AND WEIGHT**

#### ***Motor Vehicle Act* regulations apply**

- 91 Division 35 of the Motor Vehicle Act Regulations of the *Motor Vehicle Act*, B. C. Reg. 26/58 (Cargo Securement) apply with the necessary changes and as applicable, to the driving or operation of a vehicle on a street.

#### **Vehicle size and weight**

- 92 (1) Division 7 (Size and Weight) of the Commercial Transport Act Regulations of the *Commercial Transport Act*, B.C. Reg. 30/78, apply with the necessary changes and as applicable, to regulate the size and weight of a vehicle that is driven or operated on a street.
- (2) For the purposes of interpreting section 93 and Division 7 referred to in subsection (1), the following definitions apply:
  - (a) section 1 of the *Motor Vehicle Act*;
  - (b) section 1 of the *Commercial Transport Act*;
  - (c) Division 1 of the *Motor Vehicle Act* Regulations, for Cargo Securement, (Division 35 of British Columbia Regulation 26/58);
  - (d) Division 1 of the *Commercial Transport Act* Regulations, for Size and Weight (Division 1 of British Columbia Regulation 30/78).
- (3) The definitions under subsection (2)(d) prevail if there is an inconsistency among the definitions under subsection (2).
- (4) Despite any other provision of this Bylaw, including a regulation referred to in subsection (1), a person may drive, operate, or permit the driving or operation of

- (a) a vehicle or combination of vehicles with a licensed gross vehicle weight on any group of axles of 22,680 kg. or less, on any street, or
  - (b) a commercial vehicle, as defined under subsection (2)(b) with a licensed gross vehicle weight on any group of axles of more than 22,680 kg, on a street shown in Schedule D.
- (5) The penalties and offence provisions applicable to the regulations referred to in subsection (1) do not apply to the enforcement of those regulations for the purposes of this Bylaw.

***Commercial Transport Act regulations apply to all vehicles***

- 93 (1) The regulations and the definitions respectively referred to in subsections 92(1) and (2) apply to all vehicles as if they were the commercial vehicles referred to in those regulations and definitions.
- (2) Despite section 92, the City's Director of Engineering or a person authorized by the City's Director of Engineering may issue a permit to authorize the driving or operation of a vehicle that contravenes the regulations prescribed under those sections.
- (3) For the purposes of subsection (2), the City's Director of Engineering or a person authorized by the City's Director of Engineering may
- (a) issue a permit,
  - (b) limit the time during which a permit is valid, and
  - (c) establish terms and conditions of a permit.

**Engineer's report for permit**

- 94 As a prerequisite to the issuance of a permit under this Part, the Director of Engineering may require an applicant for the permit to submit a report by a British Columbia Professional Engineer concerning any aspects of the proposed use of a City street.

**PART 5 - GENERAL REGULATIONS**

**Parking commercial vehicle in residential zone**

- 95 (1) A person must not park or permit to remain parked a commercial vehicle with a licensed gross vehicle weight in excess of one ton in front of land zoned for residential purposes under the City's Zoning Regulation Bylaw or Zoning Bylaw 2018, between the hours of 6:00 p.m. of one day and 7:00 a.m. of the next day.
- (2) Subsection (1) does not apply to a commercial vehicle parked contrary to subsection (1) if it is there for the purpose of enabling its driver or user to perform a commercial service that cannot conveniently be performed otherwise.
- (3) A person who carries on a business in or from a house on land in a zone under the City's Zoning Regulation Bylaw or Zoning Bylaw 2018 which permits single

family dwellings or duplexes, must not at any time park or allow to be parked more than two commercial vehicles in a street in that zone.

- (4) A person must not park or permit to remain parked a charter bus or a sightseeing bus in front of land zoned for residential purposes under the Zoning Regulation Bylaw or Zoning Bylaw 2018.

#### **Trailer left on street**

- 96 A person must not leave, or permit to be left, a trailer on a street unless it is
  - (a) authorized by a permit issued under section 107, or
  - (b) attached to a motor vehicle.

#### **Driving between vehicles in funeral procession**

- 97 (1) The driver of a vehicle must not drive between vehicles in a funeral procession or any other authorized procession while it is in motion unless obeying the directions of a traffic control device or a police officer.
- (2) For the purposes of this section, during daylight hours a vehicle is considered not to be in a procession unless the headlights of the vehicle are lighted.

#### **Air horn**

- 98 (1) Despite the Noise Abatement Bylaw, the driver, operator, or other person in charge of a motor vehicle equipped with an air horn must not sound or permit the air horn to be sounded in the City at any time.
- (2) The driver, operator, or other person in charge of a vehicle equipped with a horn that is not an air horn must not sound or permit it to be sounded in the City except
  - (a) as required under the *Motor Vehicle Act*, or
  - (b) for the purpose of giving reasonable warning to persons using or about to use a street, of a hazard or danger arising out of the presence or approach of the vehicle.
- (3) Subsection (1) does not apply to the driver, operator, or any other person in charge of an emergency vehicle.

#### **Procession in street requires permit**

- 99 (1) A person must not be a member of or take part in a procession through, in, on, over or above a street unless a permit for the procession has been issued under an order of the Director of Engineering.
- (2) For safety purposes, the Director of Engineering may impose terms and conditions on a permit issued under this section.

### **Commercial goods on street**

- 100 (1) A person must not permit any goods, merchandise, or any other articles of trade or commerce to remain on any part of a street longer than is reasonably necessary to deliver them expeditiously or to remove them into a vehicle.
- (2) Despite subsection (1), a mobile bicycle vendor may sell commercial goods on the street as defined in Schedule I.

### **Excavations, obstructions on street require permit**

- 101 (1) A person must not do any of the following activities unless the person first obtains a permit from Council, who may impose conditions on the permit:
- (a) excavate in, disturb the surface of, or cause a nuisance in, on, over, under or above a street or other public place;
  - (b) encumber, obstruct, injure, foul or damage a street, a sidewalk, or another public place;
  - (c) do anything that is likely to cause anything described in paragraph (b).
- (2) Subsection (1) does not apply to any of the following persons or objects:
- (a) employees or agents of the City while they are acting in the course of their employment;
  - (b) articles of trade or commerce lawfully in a street or other public place;
  - (c) a portable sign permitted under section 102A of this Bylaw;
  - (d) electric vehicle charging works for which a licence has been entered into under section 105A of this Bylaw;
  - (e) works for which a permit is issued under this section or section 106 of this Bylaw, or under a bylaw passed under section 14 of the *Victoria City Act, 1919*.
- (3) The holder of a permit issued under this section must comply with the terms and conditions contained in it.
- (4) The City Manager may issue a permit for the purposes of this section
- (a) in cases of urgency,
  - (b) where an obstruction is minor or inconsequential, or
  - (c) where an obstruction is not likely to continue for more than 72 hours.

## Objects prohibited on streets

102 (1) Without limiting the generality of section 101(1),

BL 23-054

- (a) A person must not place, or cause or permit to be placed or left, any of the following items so as to occupy, obstruct, or cause a nuisance on any part of a street, sidewalk or other public place:
  - (i) any property or thing, or
  - (ii) a sign, as defined in the Sign Bylaw.
- (b) [Repealed]
- (c) a person must not place or cause or permit to be placed on, above or in a street, sidewalk, or other public place waste matter of any description, including without limitation, litter, rubbish, garbage, offal, filth, or any noxious, offensive or unwholesome substance or matter;
- (d) a person must not distribute or deliver, or cause or permit to be distributed or delivered in or near any street, sidewalk, or other public place, a pamphlet or any other printed or written matter for the purpose of publicizing an event, fact, product, or thing if the probable result of that action is
  - (i) the matter will be discarded on a street, sidewalk, or other public place by a person receiving the matter, or
  - (ii) passage in or on a street will be impeded or obstructed.

(2) Subsection (1) does not apply to any of the following persons or objects:

- (a) employees or agents of the City while they are acting in the course of their employment;
- (b) articles of trade or commerce lawfully in a street or other public place;
- (c) a portable sign permitted under section 102A of this Bylaw;
- (d) electric vehicle charging works for which a licence has been entered into under section 105A of this Bylaw;
- (e) works for which a permit is issued under section 101 or 106 of this Bylaw, or under a bylaw passed under section 14 of the *Victoria City Act, 1919*.

24-077

(3) The Director of Engineering, a person authorized by the Director of Engineering, a bylaw officer, or a police officer, may remove, seize, and impound or cause the removal, seizure or impoundment of any property or thing that unlawfully occupies, or has been unlawfully placed or left in, a street, sidewalk or public place, and such item will be dealt with in accordance with the Property in Custody Bylaw.

- (4) An action taken under this section does not preclude the prosecution of a person who contravenes a provision of this Bylaw.

### **Portable signs**

- 102A (1) In this section:

“arcade”

means two or more ground floor businesses located within a single building or property that are accessed from the sidewalk through a common entrance or pathway;

“Licence Inspector”

means a person appointed by Council as a business licence inspector;

“park”

has the same meaning as in the Parks Regulation Bylaw except it does not include Bastion Square or Centennial Square;

“portable sign”

means a sign which is self-supporting and easily moved;

“portable sign permit”

means a permit issued under subsection (3) or renewed under subsection (4); and

“sign”

has the same meaning as in the Sign Bylaw.

- (2) A person must not place, construct, erect or cause or permit to be placed, constructed or erected a portable sign that encroaches on, obstructs, or otherwise occupies any public place or sidewalk without first obtaining a portable sign permit.
- (3) The Licence Inspector must issue a permit for the placement of a portable sign on a sidewalk or other public place, other than a park, provided that:
- (a) a valid Business Licence for the business the portable sign relates to has been issued pursuant to the *Business Licence Bylaw*;
  - (b) the applicant has submitted an application in the form prescribed by the Licence Inspector;
  - (c) the applicant has paid:

- (i) a non-refundable application fee of \$30.00 plus applicable taxes; and
    - (ii) a non-refundable annual use of public space charge of \$5.00 plus applicable taxes;
  - (d) the Licence Inspector is satisfied that the proposed portable sign and its location otherwise comply with the requirements of this section; and
  - (e) a portable sign permit for the business the sign relates to has not been issued already.
- (4) The Licence Inspector must renew a permit for the placement of a portable sign on a sidewalk or other public place, other than a park, provided that:
- (a) the applicant held a valid portable sign permit for the same portable sign and address in the previous year;
  - (b) the Business Licence for the business the portable sign relates to has been renewed;
  - (c) the applicant has paid:
    - (i) a non-refundable annual permit fee of \$30.00 plus applicable taxes; and
    - (ii) a non-refundable annual use of public space charge of \$5.00 plus applicable taxes;
  - (d) the Licence Inspector is satisfied that the portable sign and its location continue to comply with the requirements of this section; and
  - (e) a portable sign permit for the business the sign relates to has not been renewed already.
- (5) A single portable sign, advertising one or more businesses located in an arcade, may be displayed at an entrance to the arcade provided that:
- (a) the owner, or representative of the owner, of the arcade applies for a portable sign permit;
  - (b) every business advertised on the sign has a valid Business Licence; and
  - (c) all other provisions of this section are complied with, as if the arcade was a single business.
- (6) A portable sign permit expires on January 15 of the year immediately following the year for which it had been issued or renewed.
- (7) A portable sign permit must specify the address where the portable sign may be placed and is not valid for any other address.

- (8) Notwithstanding subsections (3) and (4), the Licence Inspector must not issue or renew a portable sign permit unless:
- (a) the business the sign relates to has a dedicated and direct access to the business from the sidewalk.
  - (b) the sidewalk in front of the business the sign relates to is at least 2.6 meters in width;
  - (c) the business the sign relates to has at least 1.5 meter street frontage on the sidewalk where the portable sign is located;
  - (d) if the portable sign is to be located in Bastion Square or Centennial Square, the Director of Parks, Recreation and Culture, having considered the other permitted uses and planned activities, has consented to the issuance of the permit; and
  - (e) the applicant maintains valid liability insurance in respect of the portable sign in an amount of at least \$2,000,000.
- (9) A portable sign must be placed:
- (a) in front of:
    - (i) the business it relates to, or
    - (ii) the entrance to the arcade, if the sign relates to a business or businesses located in the arcade.
  - (b) either:
    - (i) as close to the property line of the business it relates to as practical; or
    - (ii) as close to the curb as practical but no closer than 0.3 meters from the curb;
  - (c) at least 2 meters from another portable sign;
  - (d) at least 1.5 meters from any works; and
  - (e) in such a way that it does not:
    - (i) impede pedestrian or vehicular traffic;
    - (ii) leave less than 2 meters of sidewalk width clear for pedestrians and other users of the sidewalk;
    - (iii) restrict access to and egress from vehicles lawfully parked or stopped on a street;

- (iv) interfere with the use of any City infrastructure, including street furniture and bus stops; or
  - (v) cause any damage to City property.
- (10) A portable sign must not:
  - (a) be displayed when the business the sign relates to is not open to the public;
  - (b) be illuminated;
  - (c) be attached to the ground, a building or other structure, or any type of conveyance;
  - (d) exceed 60 cm in width, 60 cm in depth and 90 cm in height;
  - (e) have more than 80% of the sign area used for changeable text;
  - (f) be placed on a sidewalk until snow and ice has been removed in accordance with section 107(2) of this Bylaw;
  - (g) have anything attached to it, including but not limited to balloons, pamphlets, pennants or flags; or
  - (h) display any advertising other than that related to the business in front of which it is located or, if the sign is located in front of an entrance to an arcade, the businesses located in that arcade.
- (11) The holder of the portable sign permit must, at all times the portable sign is displayed on a street or in a public place, maintain the sign in a safe and clean condition and in good repair.
- (12) The holder of the portable sign permit must affix to the portable sign a decal issued by the Licence Inspector at the time the portable sign permit is issued or renewed and write the portable sign permit number on the decal in such a way that it is clearly visible and legible.
- (13) The Licence Inspector or a Bylaw Officer may impound or cause to be impounded any portable sign that does not display a decal with a valid permit number as required by subsection (12) or otherwise contravenes this section, and the portable sign will be dealt with in accordance with the Property in Custody Bylaw.
- (14) On an application of the holder of the portable sign permit and payment of a replacement fee of \$10, the Licence Inspector may issue a replacement decal if the Licence Inspector is satisfied that the original decal has been lost or damaged.

- (15) The Director or a person authorized by the Director may request the portable sign permit holder, or the person in charge of the business to which the sign relates, to temporarily remove the portable sign for any reason, including:

24-024

(a) street cleaning;

(b) installation, maintenance, service or repair of City property or any infrastructure;

24-024

(c) construction activity on the street;

(d) any emergency where the Director or a person authorized by the Director determines that the circumstances require the sidewalk to be kept clear of obstructions; or

(e) to accommodate another permitted event or activity on a City street or in a public place, and

the portable sign permit holder, or the person in charge of the business to which the sign relates, shall promptly remove the portable sign.

- (16) Notwithstanding any other provision of this section, only one portable sign shall be displayed, at any one time, for each business or arcade.

### **Obstructing sidewalk, soliciting, fighting**

- 103 (1) Without limiting the generality of section 101, a person must not obstruct a sidewalk by squatting, kneeling, sitting, or lying down on it between the hours of 8:00 a.m. and 9:00 p.m. of the same day if the sidewalk is located at any of the following locations:

(a) in the area that is bounded by Cook, Pembroke, Store, Wharf, Government, Superior and Southgate Streets;

(b) abutting or adjacent to those parts of Cook, Pembroke, Store, Wharf, Government, Superior and Southgate Streets that form the boundary of the area referred to in paragraph (a).

- (2) The prohibition set out in subsection (1) does not apply to circumstances that involve any of the following activities or objects:

(a) a medical emergency or wheelchair;

26-024

(b) sitting on a seat at a transit zone while waiting for a bus;

(c) sitting on a chair or bench that is supplied by a public agency or an abutting private property owner and that is permitted by a street use permit issued by the City;

(d) sitting at a sidewalk café that is licensed under the Sidewalk Cafes Regulation Bylaw;

26-044

- (e) sitting while engaged in the activity of a hawker, peddler, or street entertainer who is licensed for that purpose under the Street Entertainment Bylaw and the Business Licence Bylaw;
  - (f) a parade, rally, demonstration, performance, or gathering that is permitted by a street use permit issued by the City;
  - (g) the soliciting of aid by an organization that holds a valid permit issued for that purpose under the Street Collections Bylaw, 1977.
- (3) Subsection (1) is not intended to create a result through enforcement that is absurd or unreasonable.
- (4) In this subsection and subsection (5),

“automated teller machine”

means a device that is linked to a financial institution’s account records, and that is able to carry out transactions that include account transfers, deposits, cash withdrawals, balance inquiries, payments of amounts owed, or other financial transactions;

"cause an obstruction"

means:

- (a) to sit or lie on a street in a manner which obstructs or impedes the convenient passage of any pedestrian traffic in a street, in the course of solicitation,
- (b) to continue to solicit from or otherwise harass a pedestrian after that person has made a negative initial response to the solicitation or has otherwise indicated a refusal,
- (c) to physically approach and solicit from a pedestrian as a member of a group of 3 or more persons,
- (d) to solicit on a street within 6 m of
  - (i) an entrance to a bank, credit union, or trust company,
  - (ii) an automated teller machine, or
  - (iii) a parking ticket dispensing machine, or
- (e) to solicit from an occupant of a motor vehicle in a manner which obstructs or impedes the convenient passage of any vehicular traffic in a street;

"solicit"

means, without consideration, to ask for money, donations, goods, or other things of value whether by spoken, written or printed word or bodily gesture, for one's self or for any other person, and solicitation has a corresponding meaning, but does not include soliciting for charity

- (a) by the holder of a permit for soliciting for charity under the Street Collections Bylaw, 1977, and
- (b) by the holder of a licence for soliciting for charity under the provisions of the Business Licence Bylaw;

"trust company"

means an office or branch of a trust company to which the *Trust and Loans Company Act (Canada)* applies and in which deposit accounts are held.

- (5) A person must not solicit in a manner that causes an obstruction.
- (6) A person must not obstruct or create a nuisance upon any portion of a street or other public place by participating in a consensual fight or other similar physical confrontation between consenting adults.

## **Boulevards and medians**

103A (1) In this section:

"boulevard"

includes:

- (a) on a street with curbs, the unpaved portion of street between the outside curb and adjoining property line; and
- (b) on a street without a curb, the unpaved portion of street between the edge of the roadway and the adjoining property line.

"median"

includes:

- (a) an area that is painted, curbed or raised and is located between traffic lanes to separate vehicles travelling in opposite directions;
- (b) any unpaved portion of the road allowance, including but not limited to landscaped areas and greens, located between two or more roadways or streets; and
- (c) a traffic circle or other traffic divider.

"roadway"

means that portion of a street improved, designed or intended for vehicular use.

- (2) A person must not place, construct, erect or cause or permit to be placed, constructed or erected any structure, tent, object or thing that encroaches on, obstructs, or otherwise occupies a boulevard or median without first obtaining written permission from the Director of Engineering.
- (3) Subsection (2) does not apply to any of the following persons or objects:
  - (a) employees or agents of the City while they are acting in the course of their employment;
  - (b) a special event for which a permit has been issued by the Director of Parks and Recreation;
  - (c) works for which a permit is issued under section 102 or 106 of this Bylaw, or under a bylaw passed under section 14 of the *Victoria City Act, 1919*; and
  - (d) boulevard gardening to the extent permitted pursuant to subsection (10).
- (4) The Director of Engineering, a person authorized by the Director of Engineering, a Bylaw Officer, or a member of a police force, on behalf of the City may cause the removal, detention or impounding of any structure, tent, object or thing found on a boulevard or median in contravention of this section, and the portable sign will be dealt with in accordance with the Property in Custody Bylaw.
- (5) Between sunset of one day and sunrise on the next day, a person must not:
  - (a) occupy a median by squatting, kneeling, sitting, or lying down on it;
  - (b) stand or walk on a median except while lawfully crossing a street.
- (6) The prohibition set out in subsection (5) does not apply to any of the following:
  - (a) employees or agents of the City while they are acting in the course of their employment;
  - (b) police officers in the performance of their duties;
  - (c) a medical emergency;
  - (d) sitting on a seat, or standing, at a transit zone while waiting for a bus;
  - (e) persons participating in or attending a special event for which a permit has been issued by the Director of Engineering or the Director of Parks and Recreation;
  - (f) walking on a path or trail designed for that purpose;

26-024

BL 23-054

26-024

BL 23-054

- (g) persons sitting on a seat or squatting, kneeling, walking or standing while recreating within the fenced portion of a median designated as a leash-optional area during the hours permitted in the Animal Responsibility Bylaw.
- (7) A person must not do any of the following on a boulevard:
  - (a) cut, break, injure, remove, climb, or in any way destroy or damage
    - (i) a tree, shrub, plant, turf, flower, or seed, or
    - (ii) a building or structure, including a fence, sign, seat, bench, or ornament of any kind;
  - (b) dispose of household, yard, or commercial waste.
- (8) Prohibition contained in subsection (7)(a) does not apply to any of the following:
  - (a) employees or agents of the City while they are acting in the course of their employment; and
  - (b) persons acting under an agreement with the City or a permit issued by the Director of Parks and Recreation..
- 26-024 (9) For certainty, this section applies to any boulevard and median that is also a park, notwithstanding section 17 of the Parks Regulation Bylaw.
- (10) A person may plant or maintain a garden on a boulevard, provided:
  - (a) the person owns or occupies the property immediately adjacent to the portion of boulevard which the person is gardening,
  - (b) the person provides the City's Director of Parks and Recreation written notice of that person's intention to garden in the boulevard 30 days prior to commencing any gardening activities,
  - (c) the notice set out in paragraph (b) includes the person's full name, address and telephone number where that person can be contacted,
  - (d) the person does not
    - (i) install any permanent structures on the boulevard, including but not limited to irrigation systems and affixed ornaments,
    - (ii) cut or otherwise damage the roots, trunks, bark or branches of the boulevard trees, or
    - (iii) affix signs, trellises or other objects to a boulevard tree,
  - (f) none of the garden beds:

- (i) exceed 8m in length or width, or
    - (ii) are raised in excess of 45cm,
  - (g) all plants and garden beds are at least:
    - (i) 60cm from any curb adjacent to a permitted parking area, and
    - (ii) 1.5m from fire hydrants, utility poles, bus shelters, concrete bus pads,
  - (h) none of the garden plants:
    - (i) impede sightlines for pedestrians or vehicles.
    - (ii) hang over or grow into a street,
  - (i) upon receiving notice from the City's Director of Parks and Recreation that any or all of the garden obstructs or interferes with the sight-lines, mobility or safety of vehicles or pedestrians, the person trims, alters or removes the boulevard garden, or portions thereof, to the satisfaction of the City's Director of Parks and Recreation,
  - (j) the person keeps the garden well-maintained, and
  - (k) that when the garden maintenance stops, that person removes the garden and returns the area to the state it was in immediately before the garden was planted.
- (11) If a person who planted or maintained a boulevard garden does not comply with subsection (10), the City may, at any time, cause the boulevard garden area to be brought into compliance, and that person shall pay to the City the fee specified in Schedule "F" of this bylaw."

24-024

## Fireworks

- 104 A person may explode fireworks in a street or other public place only in accordance with the Fireworks Bylaw.

## Liquids onto street require permit

- 105 (1) A person owning or occupying property which abuts on, or is contiguous with, a street may permit a liquid substance to flow from the property onto or over the street only if that person first obtains a permit from the Director of Engineering.
- (2) For safety purposes, the Director of Engineering may impose terms and conditions on a permit issued under this section.
- (3) The person to whom a permit is issued under this section must observe and perform the terms and conditions imposed by the permit.

24-077

### **Electric vehicle charging infrastructure on street**

- 105A (1) Council delegates to the Director of Engineering the authority to enter into and execute licence agreements allowing owners and occupants of residential property that abuts on, or is contiguous with, a street, to lay electric vehicle charging cords across sidewalk and boulevard adjacent to their property for the purpose of charging their electric vehicles, in accordance with the conditions set out in this section.
- (2) Any licence permitted under this section must be:
- (a) for a one year term,
  - (b) consistent with any policy developed by the Director of Engineering in consultation with the City's Accessibility Advisory Committee, or a successor organization serving similar purposes, and
  - (b) in a form acceptable to the City Solicitor.
- (3) The Director of Engineering may impose terms and conditions on a licence permitted under this section.
- (4) The delegation to the Director of Engineering under this section includes the authority to exercise on behalf of the City any rights contained in any licence entered into pursuant to this section, and to amend, renew and terminate a licence pursuant to this section.
- (5) A person must not lay down or cause or permit to be laid down an electric vehicle charging cord or associated works that encroaches on, obstructs, or otherwise occupies any public place or sidewalk unless they obtain a licence pursuant to this section and strictly comply with the terms and conditions of the licence.
- (6) A Bylaw Officer may impound or cause to be impounded any electric vehicle charging cord or associated works that is not licensed as required by subsection (5) or is not in compliance with the terms of the licence, and it will be dealt with in accordance with the Property in Custody Bylaw.

### **Works on street require permit**

- 24-024 106 (1) The Director of Engineering may issue a written permit for the obstruction of a street for any of the following purposes:
- (a) removal of a building, structure or object;
  - (b) repair, alteration, or reconstruction of a building;
  - (c) for any other necessary work.
- 24-024 (2) A person must not occupy any part of a street for a purpose mentioned in subsection (1) if that person does not have a permit issued under subsection (1).
- 24-024 (3) An applicant for a permit to occupy a street must
- 24-024

- (a) in the application, state the period for which it is expected that the permit is required and provide any other information, including but not limited to a traffic control plan or traffic management plan if required by the Director and in a form prescribed by the Director;

24-024

- (b) pay to the City the following fees that apply to the occupation:

- (i) for each 13m<sup>2</sup> of a street or portion thereof:

- (A) \$10.00 per day on a boulevard;
- (B) \$15.00 per day on any part of a street not otherwise listed in this subsection 106(3)(b);
- (C) \$20.00 per day on a sidewalk;
- (D) \$20.00 per day in a metered zone or a pay station zone;
- (E) \$140.00 per day where a charging station or car share EV station is affected, and the aforesaid is a direct current fast charging station providing at least 50 kilowatts of direct current electrical power;

24-077

- (ii) In addition to the fee required under subparagraph (b)(i), if the occupation requires closure of a travelled portion of the street, the following fees must be paid to the City:

- (A) for closure of a protected bicycle lane , the greater of \$100 per day or the applicable rate per day per closure as set out in subparagraph (b)(ii)(B);
- (B) for closure of a sidewalk or any lane that is not a protected bicycle lane :
  - a. \$50 per day on a local street;
  - b. \$75 per day on a collector street;
  - c. \$250 per day per sidewalk or any lane on an arterial street;

- (iii) \$50.00 for each attendance of a City crew during the crew's regular working hours that is required for installation or removal of signs to reserve the space in connection with the occupation of a street;

- (iv) \$50 for each application submitted within 48 hours the proposed start of the proposed occupation, regardless of whether the permit is issued within 48 hours of the City receiving the application;

- (v) the actual cost of a City crew that is required for traffic control measures other than those set out in subparagraph (b)(iii) in connection with the occupation of a street; and

- (vi) \$70 per hour or portion thereof for traffic management plan or traffic control plan review by City staff.
- (4) The applicant for a permit must pay, in advance, the applicable fees specified in subsection (3)(b)(i) to (iv).
- 24-024 (5) The City must provide an applicant with an estimate of the costs described in subparagraphs (3)(b)(v) and (vi).
- 24-024 (6) A permit holder must satisfy the following requirements if that person's degree of occupancy of a street is required to change during the progress of that person's work on the street:
  - (a) obtain the approval for an extension or modification of occupancy from the Director of Engineering;
  - (b) pay any additional fee required in accordance with subsection (3).
- (7) The Director of Engineering may reserve for the sole use of any permit holder, during the period in which the permit is in force, curb space for necessary access and loading purposes opposite the building for which the permit is issued.
- (8) The fees prescribed by this section are due to the City whether or not a permit has been issued.
- 24-024 (9) The holder of a permit issued under this section must comply with each condition of the permit, including but not limited to the terms and conditions of any required traffic management plan or traffic control plan.
- (10) The Director may cancel a permit issued under this section immediately, and without prior notice, if in the opinion of the Director the permit holder fails to comply with any of the conditions of the permit, including but not limited to the terms and conditions of any required traffic management plan or traffic control plan.

#### **Damage to survey monuments fee**

106A A person who damages, destroys, or moves a survey monument located within a street, sidewalk, boulevard, or public place, must pay the City a fee of \$2,000 to replace or restore the survey monument.

#### **Clearing sidewalk of snow and ice**

- 107 (1) In this section, "occupier" means a person who occupies land, but does not include the occupier of a unit in an apartment, hotel or institution.
- (2) The owner or occupier of land must remove snow and ice from a sidewalk bordering that land before 10:00 a.m. of each day.

- (3) The owner or occupier of land must remove, from all roofs and other parts of structures located on that land, snow, ice, and rubbish that is hazardous to the use of an adjacent highway or sidewalk.
- (4) Owners and occupiers of land must not use corrosive materials for removing snow or ice on a sidewalk.

### **Placing wood on a street**

- 108 (1) A person must not place wood, sawdust, or coal on a street if it is likely to be an obstruction to users of the street.
- (2) A person to whom wood, sawdust, or coal has been delivered must not permit it to remain on a street for longer than 24 hours.

### **Paint, posters on street structure**

- 24-024 109 (1) A person must not do any of the following acts on a street or a sidewalk, or on a structure or fixture that is in or on a street:
  - (a) paint, draw, or write;
  - (b) place a notice, handbill, poster or advertisement;
  - (c) mark or disfigure in a manner not referred to in paragraphs (a) and (b).
- (2) Subsection (1) does not apply to any of the following matters:
  - (a) an agreement or regulation made under the *Victoria City Act, 1919*, that authorizes a person to do any of the acts prohibited by subsection (1);
  - (b) any placement of marks, letters or symbols during the execution of authorized work in a street or on a sidewalk.
- (3) Subsection (1)(b) does not apply to the placing of a notice, handbill, poster or advertisement on any of the following structures:
  - (a) a poster cylinder installed on a City lamp post for the purpose of affixing posters and advertisements;
  - (b) a poster board installed at the entrance to a City parkade.
- (4) Subsection (1)(a) does not apply to chalk drawings and writings on a sidewalk on Yates Street between Blanshard and Douglas Streets on July 1.
- (5) For the purposes of the City's enforcement of this section,
  - (a) evidence that a notice, handbill, poster, or advertisement was placed contrary to the provisions of this section may be treated as evidence that the notice, handbill, poster, or advertisement was placed by the person who caused or authorized that placing, and

- (b) in the absence of evidence to the contrary, a person, business, or mercantile, commercial or other establishment that is promoted by a notice, handbill, poster or advertisement may be presumed to have authorized and caused its placing.

### **Parking on sidewalk or boulevard requires permit**

- 110 A person may cause or permit a vehicle to stop, stand, or park on a sidewalk or boulevard only in accordance with the terms and conditions, applicable for the purposes of safety, of a permit issued by an order of the Director of Engineering.

### **Driving on sidewalk permitted in special circumstances**

- 26-024 111 (1) A person may drive a vehicle on that portion of a sidewalk or boulevard that does not lie within a driveway crossing only
- (a) in accordance with the terms and conditions, applicable for the purposes of safety, of a permit issued by order of the Director of Engineering,
  - (b) when entering or leaving a driveway or lane, or
  - (c) when entering on or leaving land that is adjacent to a street.
- (2) A person must not drive a vehicle on or over a curb.

### **Trees on and near streets**

- 112 (1) A person must not plant a tree, hedge, bush, or shrub closer than 45 cm to a street line.
- (2) The owner or occupier of land adjacent to a street must
- (a) trim and cut back a tree, hedge, bush, or shrub on the owner's land to prevent injury to a roadbed, sidewalk or other works or obstruction to or interference with the free use of the street by persons or vehicles; and
  - (b) trim, remove, or cut down a tree, hedge, shrub, or bush (collectively "tree") on the owner's land within 5 days of receiving notice from the Director of Parks and Recreation (the "Director") to do so and that the Director considers the tree to be injurious to a roadbed, sidewalk or other works or an obstruction to or interference with the free use of the street by persons or vehicles.
- (3) The notice under subsection (2) (b) must contain a copy of subsection (4), as notice of the consequences of failure by the owner or occupier to act according to the notice.
- (4) (a) In accordance with sections 16(6)(b) and 17 of the *Community Charter*, if an owner or occupier does not take an action required by a notice given under subsection (3), the City may enter upon the land to take or have the required action taken.

- (b) The Director of Parks and Recreation, or any person authorized by that Director, is authorized to enter on land in the manner authorized by section 16 of the *Community Charter* for the purpose of clause (a) of this subsection.
  - (c) An action taken by the City under this subsection is at the expense of the owner or occupier, and the City may recover the costs incurred in doing so as a debt from the owner or occupier in accordance with section 17 of the *Community Charter*.
  - (d) In accordance with section 258 (1)(c) of the *Community Charter*, if the City takes action and the costs of the action are unpaid on December 31 in the year in which they are incurred, they are deemed to be taxes in arrear.
- (5) Council may take remedial action under Part 3, Division 12 of the *Community Charter* with regard to dangerous or hazardous trees on private property, as authorized under section 73 of the *Community Charter*.

#### **Private streets and lanes require sign**

- 113 The owner of land forming a private street or lane must at all times exhibit, at its junction with any public street, a sign bearing the words "Private Lane" in letters that are at least 8 cm high.

#### **26-024 Cycles on sidewalks, bicycle helmets**

- 114 (1) In this section, "bicycle safety helmet" means a helmet that
- (a) is designated as an approved bicycle safety helmet under section 184 of the *Motor Vehicle Act*, or
  - (b) meets the standards and specifications prescribed under section 184 of the *Motor Vehicle Act*.

26-024

- (2) A person must not ride or operate a cycle on or across
- (a) a sidewalk, or
  - (b) a street or path in a public place where signs are displayed stating that the street or path is for pedestrian traffic only.
- (3) Subsection (2) does not apply to
- (a) a police officer who is carrying out the officer's duty, while pursuing an offender, or while acting during an emergency, or
  - (b) a member of the British Columbia Ambulance Service Paramedic Bike Squad who is carrying out the member's duty while making medical assistance available to the public.

26-024

- (4) Subject to subsection (2), a person may operate or ride as a passenger on a cycle on a path or way that is not a highway and that is not located on private property only if that person is properly wearing a bicycle safety helmet.
- (5) Subject to subsection (2), a parent or guardian of a person under the age of 16 years may authorize or knowingly permit a person to operate or ride as a passenger on a cycle on a path or way that is not a highway and that is not located on private property only if the person is properly wearing a bicycle safety helmet.

### **Skating on sidewalk**

- 115 (1) A person must not use a skateboard, roller skates, in-line skates, or a non-motorized scooter on a sidewalk unless
  - (a) permitted to do so by a sign, and
  - (b) the person exercises due care and attention and reasonable consideration for other persons using the sidewalk.
- (2) A person must not use a skateboard, roller skates, in-line skates, or a non-motorized scooter on a street or path in a public place where signs are displayed stating that the street or path is for pedestrian use only.

26-044

### **[Repealed]**

- 116 [repealed]

## **PART 6 - ADMINISTRATION AND ENFORCEMENT**

### **Chalk mark on vehicle tire**

- 117 A person must not remove, from the tire of a vehicle, a chalk mark being used for the purpose of enforcing a parking provision of a bylaw of the City.

26-044

### **[Repealed]**

- 118 [repealed]

### **Offence**

- 119 (1) A person who contravenes a provision of this Bylaw is guilty of an offence and is subject to the penalties imposed by the Ticket Bylaw, this Bylaw and the *Offence Act*.
- (2) Each day that a contravention of a provision of this Bylaw occurs or continues shall constitute a separate offence.

## Penalties

- 120 (1) The minimum penalties for offences under sections 19 to 44 are prescribed in Schedule E.
- (2) The minimum penalties for offences under this bylaw, except offences mentioned in subsection (1), are prescribed in Schedule F.

## Offence Notice

- 121 (1) An offence notice may be delivered to another person by a person who
- (a) is authorized by or under a resolution of the Council, or under a subsisting contract with the City, and
  - (b) has reason to believe that the other person has committed an offence under this Bylaw.
- (2) An offence notice may be delivered by
- (a) leaving it on the vehicle with which the notice is concerned, or
  - (b) giving it to the person who is believed to have committed an offence.
- (3) An offence notice may indicate the alleged offence and the amount of the voluntary penalty that may be paid to the City in respect of the alleged offence.
- (4) A prosecution must not be started for the alleged offence described in an offence notice if the voluntary penalty for that alleged offence is paid in accordance with this Bylaw before an information is sworn and a summons is issued.

## Voluntary Penalties

- 122 (1) This section does not apply to a contravention of sections 79 or 80 by the driver of a sightseeing vehicle.
- (2) The voluntary penalties referred to in subsection 121(3) are prescribed in Schedule G.

## Repeal


- 123 Bylaw No. 92-84, the Streets and Traffic Bylaw, is repealed.

|                        |                        |        |                 |      |
|------------------------|------------------------|--------|-----------------|------|
| READ A FIRST TIME the  | <b>12<sup>th</sup></b> | day of | <b>November</b> | 2009 |
| READ A SECOND TIME the | <b>12<sup>th</sup></b> | day of | <b>November</b> | 2009 |
| READ A THIRD TIME the  | <b>12<sup>th</sup></b> | day of | <b>November</b> | 2009 |
| ADOPTED on the         | <b>26<sup>th</sup></b> | day of | <b>November</b> | 2009 |

**"ROBERT G. WOODLAND"**  
CORPORATE ADMINISTRATOR

**"DEAN FORTIN"**  
MAYOR

**SCHEDULE A**  
**Streets and Traffic Bylaw**  
**Street Classifications**



**SCHEDULE B****Streets and Traffic Bylaw****Speed Zones**

For the purposes of section 17, the speed designated in each of the following headings and as shown on the map is the maximum speed at which a motor vehicle may be driven on the streets or lanes listed under those headings and as shown on the map.

This Schedule only applies to streets or lanes or portions of streets or lanes within the City's boundaries.

**15 km/h**

- (a) Nursery Road

**20 km/h**

- (b) all City lanes

**30 km/h**

- (a) on all streets and parts of streets not shown on the map below as having a maximum speed of 15 km/h, 20 km/h, 40 km/h, or 50 km/h.



## SCHEDULE C

### Streets and Traffic Bylaw

#### Night Parking Restrictions


The following paragraphs describe the continuous boundary of the area to which the night parking restrictions in s.78 apply:

- (a) starting at a point on the Dominion Government Harbour Line, where that line intersects the northeasterly limit of the Canadian Pacific Railway Company's Wharf, on the southerly side of James Bay;
- (b) then easterly and northerly following the Dominion Government Harbour Line to the south side of Johnson Street Bridge;
- (c) then westerly along the southerly limit of the Johnson Street Bridge to a point on the Dominion Government Harbour Line on the west side of Victoria Harbour;
- (d) then northerly along the Dominion Government Harbour Line to the north side of Johnson Street Bridge;
- (e) then easterly along the northerly limit of Johnson Street Bridge to the Dominion Government Harbour Line on the east side of Victoria Harbour;
- (f) then northerly along the said Dominion Government Harbour Line to a point on the extension westerly of the centre line of Chatham Street;
- (g) then easterly along the centre line of Chatham Street to the centre line of Blanshard Street;
- (h) then southerly along the centre line of Blanshard Street to the centre line of Cormorant Street, then easterly to the centre line of Quadra Street;
- (i) then southerly along the centre line of Quadra Street to the centre line of Johnson Street;
- (j) then easterly and along the centre line of Johnson Street to a point opposite the easterly boundary of City Lot 830;
- (k) then southerly along the easterly boundary of City Lot 830 to the southeast corner of City Lot 830;
- (l) then easterly and along the northerly boundary of City Lots 819 to 812 inclusive to the westerly limit of Vancouver Street;
- (m) then southerly along the said westerly limit of Vancouver Street to the northeast corner of City Lot 801;
- (n) then westerly along the northerly boundaries of City Lots 801 to 794 inclusive to the northeast corner of City Lot 793;

- (o) then southerly along the easterly boundary of City Lot 793, to the southeast corner of City Lot 793;
- (p) then southerly and across View Street to the northeast corner of City Lot 790;
- (q) then southerly and along the easterly boundary of City Lots 790 and 773 to the southeast corner of City Lot 773;
- (r) then southerly across Fort Street to the northeast corner of City Lot 682;
- (s) then southerly and along the easterly boundary of City Lot 682 and that boundary continued to the centre line of Meares Street;
- (t) then westerly along the centre line of Meares Street to the centre line of Quadra Street;
- (u) then southerly along the centre line of Quadra Street to the centre line of Broughton Street;
- (v) then westerly along the centre line of Broughton Street to the centre line of Blanshard Street;
- (w) then southerly along the centre line of Blanshard Street to the centre line of Courtney Street;
- (x) then westerly along the centre line of Courtney Street to the point opposite the easterly boundary of City Lot 104, which point is 120', more or less, easterly from the east boundary of Douglas Street;
- (y) then southerly and following the line of the easterly boundary of the second range of City Lots east of Douglas Street, to the centre line of Burdett Avenue;
- (z) then southerly to a point on the centre line of Belleville Street which point is 120' easterly from the easterly boundary of Douglas Street;
- (aa) then westerly along the centre line of Belleville Street to the centre line of Douglas Street;
- (bb) then southerly along the centre line of Douglas Street to the centre line of Elliott Street;
- (cc) then westerly along the centre line of Elliott Street to the centre line of Government Street;
- (dd) then northerly along the centre line of Government Street to the centre line of Belleville Street;
- (ee) then westerly along the centre line of Belleville Street to the easterly limit of Menzies Street;
- (ff) then northerly along the easterly limit of Menzies Street and the easterly limit of the Canadian Pacific Railway Company's Wharf to the starting point.

**SCHEDULE D****Streets and Traffic Bylaw****Truck and Commercial Routes**

1. The streets shown in the map below are designated as truck and commercial routes within the City.
2. All commercial vehicles with a licensed gross vehicle weight greater than 22,680 kg are only permitted to travel on streets that are truck routes, subject to section 3.
3. When travelling between a truck route and the origin or destination, the commercial vehicle must follow a designated commercial route or the most direct route.
4. Sections 2 and 3 do not apply to commercial vehicles that have been issued a permit to travel on an alternate route under section 93 or another provision of this bylaw.



## SCHEDULE E

### Streets and Traffic Bylaw

#### Minimum Fines for Traffic Offences Sections 19 to 44

| <u>Description of offence</u>                                             | <u>Section</u> | <u>Fine</u> |
|---------------------------------------------------------------------------|----------------|-------------|
| Fail to obey police direction                                             | 19             | \$ 60.00    |
| Disobey traffic control device                                            | 20             | 75.00       |
| Disobey stop sign                                                         | 21(a)-(c)      | 100.00      |
| Fail to yield to pedestrian – green light                                 | 21(1)(a)(ii)   | 100.00      |
| Fail to yield to vehicle - green light                                    | 21(1)(a)(ii)   | 100.00      |
| Fail to stop for yellow light at intersection                             | 23(1)(a)       | 100.00      |
| Fail to stop for red light at intersection                                | 24(1)          | 100.00      |
| Fail to yield-right turn-red light                                        | 24(3)          | 100.00      |
| Fail to yield-left turn-red light                                         | 24(4)(b)       | 100.00      |
| Fail to stop-red light – no intersection                                  | 24(5)(a)       | 100.00      |
| Fail to yield on green arrow                                              | 25(1)(a)       | 100.00      |
| Disobey green arrow                                                       | 25(1)(a)       | 100.00      |
| Fail to stop-yellow arrow-marked<br>crosswalk                             | 25(2)(a)(ii)   | 100.00      |
| Fail to stop-yellow arrow-intersection                                    | 25(2)(a)(ii)   | 100.00      |
| Fail to yield-yellow arrow-pedestrian/vehicle                             | 25(2)(b)       | 100.00      |
| Fail to stop for red flashing light at<br>intersection                    | 26(1)(a)       | 100.00      |
| Fail to stop for red flashing light<br>-no intersection                   | 26(2)(a)       | 100.00      |
| Fail to yield to pedestrian<br>-yellow flashing light at<br>intersection  | 26(3)(a)       | 100.00      |
| Fail to yield to pedestrian<br>-yellow flashing light<br>-no intersection | 26(4)(a)       | 100.00      |
| Fail to yield to pedestrian at<br>green flashing light                    | 26(5)(a)       | 100.00      |
| Unsafe lane change                                                        | 28(a)          | 60.00       |
| Land change solid line                                                    | 28(b)          | 60.00       |
| Change lanes without signal                                               | 28(c)          | 60.00       |
| Left turn from wrong lane                                                 | 28(d)          | 60.00       |
| Right turn from wrong lane                                                | 28(e)          | 60.00       |
| Illegal pass on laned roadway                                             | 28(f)          | 60.00       |
| Slow moving in wrong lane                                                 | 28(g)          | 60.00       |
| Cross solid double line                                                   | 29(1)(a)       | 60.00       |
| Fail to keep right of double broken/<br>solid line                        | 29(1)(b)(i)    | 60.00       |
| Fail to keep right of double solid/<br>broken line                        | 29(1)(b)(ii)   | 60.00       |

|                                                                                                                            |            |        |
|----------------------------------------------------------------------------------------------------------------------------|------------|--------|
| Fail to keep right of single broken/<br>solid line                                                                         | 29(1)(c)   | 60.00  |
| Drive over newly painted lines                                                                                             | 31         | 60.00  |
| Fail to pass at safe distance                                                                                              | 32(1)(a)   | 60.00  |
| Fail to complete pass safely                                                                                               | 32(1)(b)   | 60.00  |
| Fail to yield to passing vehicle                                                                                           | 32(2)(a)   | 60.00  |
| Increase speed while being passed                                                                                          | 32(2)(b)   | 60.00  |
| Pass on right                                                                                                              | 33(1)      | 60.00  |
| Unsafe pass on right                                                                                                       | 33(2)(a)   | 60.00  |
| Pass on right off roadway                                                                                                  | 33(2)(b)   | 60.00  |
| Unsafe pass on left                                                                                                        | 34         | 60.00  |
| Pass without clear view                                                                                                    | 35         | 60.00  |
| Drive over highway divider                                                                                                 | 36(a)      | 60.00  |
| Fail to keep right on divided highway                                                                                      | 36(b)      | 60.00  |
| Unsafe U-turn                                                                                                              | 37(a)      | 75.00  |
| Prohibited U-turn                                                                                                          | 37(b)(iii) | 75.00  |
| U-turn – intersection                                                                                                      | 37(b)(iv)  | 100.00 |
| U-turn – business district                                                                                                 | 37(b)(v)   | 75.00  |
| No signal on turn                                                                                                          | 38(1)      | 75.00  |
| Inadequate signal on turn                                                                                                  | 38(2)      | 75.00  |
| Fail to signal stop or decrease in speed                                                                                   | 38(3)      | 75.00  |
| Drive vehicle without signal device                                                                                        | 39(2)      | 60.00  |
| No proper signaling equipment<br>(right hand drive)                                                                        | 40(2)      | 60.00  |
| Drive over fire hose                                                                                                       | 41         | 50.00  |
| Drive on sidewalk                                                                                                          | 42         | 50.00  |
| Ride cycle on crosswalk                                                                                                    | 43(2)(a)   | 60.00  |
| Fail to ride cycle on right                                                                                                | 43(2)(b)   | 60.00  |
| Careless cycling                                                                                                           | 43(6)      | 60.00  |
| Cycling without reasonable consideration                                                                                   | 43(6)      | 60.00  |
| Operate motorcycle not on seat                                                                                             | 44(1)      | 75.00  |
| Passenger unlawfully on motorcycle                                                                                         | 44(2)(a)   | 60.00  |
| Motorcycle passenger not lawfully seated                                                                                   | 44(2)(b)   | 60.00  |
| Permit unlawfully seated motorcycle<br>passenger                                                                           | 44(3)      | 60.00  |
| Operate motorcycle over 2 abreast                                                                                          | 44(4)      | 60.00  |
| Every offence under sections 19 to 44<br>of this Bylaw other than the sections<br>specifically enumerated in this Schedule |            | 60.00  |

## SCHEDULE F

### Streets and Traffic Bylaw

24-024

#### Minimum Fines for Traffic Offences other than Sections 19 to 44

The minimum penalties set out in the second column of the following table apply to contraventions of the corresponding sections shown in the first column of the table:

24-077

24-077

| <i>Section numbers</i>                                                                                                                                            | <i>Minimum penalties</i>                                                                                                                           |
|-------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------|
| 48, 49, 53, 54, 65, 83,<br>87(2)(d),(l)&(m), 89, 90, 110,<br>112                                                                                                  | \$40.00                                                                                                                                            |
| 50, 51, 56 to 59, 61, 63, 66 to<br>71, 72A(1), 72A(4), 72A(6),<br>72B(1), 72B(2), 75, 76, 78, 81,<br>82, 84 to 86, 87(2)(b),(c),(e) to<br>(k),(n)&(o), 88, 95, 96 | \$30.00                                                                                                                                            |
| 60                                                                                                                                                                | \$75.00                                                                                                                                            |
| 72A(5), 72B(3), 77                                                                                                                                                | \$175.00                                                                                                                                           |
| 55, 62, 72A(2), 79, 80                                                                                                                                            | \$50.00                                                                                                                                            |
| Part 4 sections, including a<br>statutory or regulatory provision<br>adopted under that Part                                                                      | \$102.50                                                                                                                                           |
| 102(1), 117                                                                                                                                                       | \$51.25                                                                                                                                            |
| 106(2), 106(9)                                                                                                                                                    | \$400                                                                                                                                              |
| 107, 109(1)(b)                                                                                                                                                    | \$100.00                                                                                                                                           |
| 114                                                                                                                                                               | \$77.50                                                                                                                                            |
| 115                                                                                                                                                               | \$57.50 for 1 <sup>st</sup> contravention<br>\$67.50 for 2 <sup>nd</sup> contravention<br>\$102.50 for 3 <sup>rd</sup> or subsequent contravention |
| provisions not referred to above                                                                                                                                  | \$42.50                                                                                                                                            |

**SCHEDULE G****Streets and Traffic Bylaw**

24-024

**Voluntary Penalties Payable under Offence Notices**

The voluntary penalties set out in the second and third columns of the following table apply to contraventions of the corresponding sections shown in the first column of the table:

|        | <i>Section numbers</i>                                                                                                                                | <i>Voluntary penalty if paid within 14 days from date of offence notice</i> | <i>Voluntary penalty if paid 15 or more days from date of offence notice</i>                                                                       |
|--------|-------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------|
|        | 48, 49, 53, 54, 65, 83, 87(2)(d),(l)&(m), 89, 90, 110, 112                                                                                            | \$40.00                                                                     | \$80.00                                                                                                                                            |
| 24-077 | 50, 51, 56 to 59, 61, 63, 66 to 71, 72A(1), 72A(4), 72A(6), 72B(1), 72B(2), 75, 76, 78, 81, 82, 84 to 86, 87(2)(b),(c),(e) to (k),(n)&(o), 88, 95, 96 | \$30.00                                                                     | \$60.00                                                                                                                                            |
|        | 60                                                                                                                                                    | \$75.00                                                                     | \$150.00                                                                                                                                           |
| 24-077 | 72A(5), 72B(3), 77                                                                                                                                    | \$175.00                                                                    | \$350.00                                                                                                                                           |
|        | 55, 62, 72A(2)                                                                                                                                        | \$50                                                                        | \$80                                                                                                                                               |
|        | 79, 80                                                                                                                                                | \$50.00                                                                     | \$100.00                                                                                                                                           |
|        | Part 4 sections, including a statutory or regulatory provision adopted under that Part                                                                | \$51.25                                                                     | \$102.50                                                                                                                                           |
|        | 102(1), 117                                                                                                                                           | \$51.25                                                                     | \$102.50                                                                                                                                           |
|        | 106(2), 106(9)                                                                                                                                        | \$875.00                                                                    | \$1000.00                                                                                                                                          |
|        | 107, 109(1)(b)                                                                                                                                        | \$50.00                                                                     | \$100.00                                                                                                                                           |
|        | 114                                                                                                                                                   | \$38.75                                                                     | \$77.50                                                                                                                                            |
|        | 115                                                                                                                                                   |                                                                             | \$57.50 for 1 <sup>st</sup> contravention<br>\$67.50 for 2 <sup>nd</sup> contravention<br>\$102.50 for 3 <sup>rd</sup> or subsequent contravention |

| <i>Section numbers</i>           | <i>Voluntary penalty if paid within 14 days from date of offence notice</i> | <i>Voluntary penalty if paid 15 or more days from date of offence notice</i> |
|----------------------------------|-----------------------------------------------------------------------------|------------------------------------------------------------------------------|
| provisions not referred to above |                                                                             | \$42.50                                                                      |

BL 23-054

Schedule H – [Repealed]

## SCHEDULE I

### Streets and Traffic Bylaw

#### CONDITIONS

##### General Conditions

A mobile bicycle vendor shall:

1. Operate a self-contained mobile bicycle vending unit. The mobile bicycle vendor shall not affix or place any tables, chairs, stools, awnings, or umbrellas to public property.
2. Only sell permitted products, including
  - a. pre-packaged foods and beverages,
  - b. unpackaged, non-potentially hazardous foods and beverages,
  - c. only dispense unpackaged foods and beverages,
  - d. non-alcoholic beverages,
  - e. flowers, and
  - f. handcrafted items made in British Columbia.
3. Only operate on City streets and parks, except Beacon Hill Park, and on designated multi-use pathways within the City of Victoria.
4. Stop on hard surfaced areas in permitted locations for up to 60 minutes.
5. Move to another location at least 2 City blocks away or 100 meters away after 60 minutes.
6. Remain 100 meters away from restaurants, events or concessions that sell a similar product.
7. Remain 30 meters away from a public or private school between 8:00 a.m. and 5:00 p.m. on school days.
8. Operate between 7:00 a.m. – 10:00 p.m. only.
9. Maintain their cycles and keep them clean and in good repair.
10. Advertise only for their business. Advertising may be integrated into the bike or mounted on the bike.
11. Install a bicycle bell, if desired, but only ring the bell for intervals of 20 seconds or fewer, and only between the hours of 9:00 a.m. – 9:00 p.m.
12. Provide an integrated waste receptacle. Recycling and compost must be separated from garbage, either as part of the cycle design or at the vendor's base of operations.
13. Comply with all applicable bylaws, including *Streets and Traffic, Park Regulation, Noise* and the *Motor Vehicle Act*.
14. Display a vending decal on each licenced cycle. The decal is non-transferable.